

THE ILLUSTRATED



ARCHITECTURAL & ENGINEERING  
DRAWING BOOK.

Bessie N. Voss

WARD AND LOCK'S  
**JUVENILE PUBLICATIONS.**

---

Demy 8vo, cloth gilt, bevelled boards, 7s. 6d., ditto, gilt edges, 8s. 6d., an entirely New Edition of

**The Swiss Family Robinson.** Specially Translated and Compiled from the best Original Editions. By HENRY FRITH. Beautifully Illustrated with Coloured Plates and upwards of 200 Engravings.

*This is one of the best editions of this delightful work yet offered to the public. No pains have been spared to make this issue of "The Swiss Family Robinson" one of the most charming of Present Books. The book is abundantly illustrated by New Coloured Pictures (which have been prepared with great care), and upwards of Two Hundred Engravings in the Text.*

---

Uniform with above, Demy 8vo, cloth gilt, 7s. 6d., ditto, gilt edges, 8s. 6d.

**Andersen's Fairy Tales.** Complete Edition. By HANS CHRISTIAN ANDERSEN. With Fourteen Coloured Pictures, and nearly 100 full-page and other Engravings, and Life of the Author.

*This is the most Complete Edition ever published of "Andersen's Fairy Tales." It is profusely illustrated, and handsomely bound, and must be acknowledged one of the very best of Children's Gift Books.*

---

Crown 8vo, 500 pp., cloth gilt, gilt edges, price 5s.

**Ice World Adventures;** or, Voyages and Travels in the Arctic Regions. By JAMES MASON. With 37 full-page Plates on toned paper, Map of the Arctic Regions, and numerous Engravings in the text.

*This book presents, in a more convenient form perhaps than any other, a complete record of the Enterprise of Civilized Man within the Arctic Circle from the Discovery of Iceland to the English Expedition of 1875, the information regarding the latter being brought down to the latest date.*

---

Imperial 16mo, 420 pp., large type, cloth extra, gilt edges, 5s.

**The Child's Popular Fairy Tales Told for the Hundredth Time.** By H. W. DULCKEN, Ph. D. With 16 Coloured Pictures and 276 other Illustrations engraved by DALZIEL Brothers, from designs by eminent artists.

*This work contains most of our old favourites in the way of Fairy Tales including:—"Tom Thumb," "The Three Bears," "Ali Baba," "Robin Hood," "Puss in Boots," "Jack and the Bean Stalk," "The Sleeping Beauty," "Little Red Riding Hood," "Jack the Giant Killer," "Cinderella," "Beauty and the Beast," "Little Goody Two Shoes," and "Aladdin."*

---

In one handsome volume, elegantly bound in cloth, bevelled boards, full gilt sides, back and edges, 21s.

**Dalziel's Illustrated Arabian Nights' Entertainments,** with upwards of 200 Pictures, drawn by J. E. MILLAIS, R.A., J. TENNIEL, J. D. WATSON, R. B. HOUGHTON, G. J. PINWELL, and T. DALZIEL, together with initial letters, ornamental borders, &c., &c. Engraved by the Brothers DALZIEL. The text emendated by H. W. DULCKEN, Ph. D.

---

London: WARD, LOCK and Co., Warwick House, Salisbury Square, E.C.



G.

WARD AND LOCK'S

## JUVENILE PUBLICATIONS.

**Andersen's Popular Tales for Children.** With many full-page and other Illustrations. Crown 8vo, cloth gilt, 3s. 6d.; with Coloured Plates, cloth gilt, gilt edges, 5s.

**Andersen's Stories for the Young.**—With many full-page and other Illustrations. Crown 8vo, cloth gilt, 3s. 6d.; with Coloured Plates, cloth gilt, gilt edges, 5s.

**The Children's Forget-Me-Not.** A Book of Pictures and Stories for the Young. Containing Stories of the Months, Tales about Animals, Seaside Ditties, &c., with upwards of 100 large Engravings. Boards, 2s. 6d.; cloth gilt, 3s. 6d.

*This charming volume has been prepared with the greatest care, and will be found to contain all that is most attractive to Little Folks. Printed in handsome type, abounding in pictures, and in a beautiful floral cover, the CHILDREN'S FORGET-ME-NOT will be acknowledged the handsomest and cheapest gift-book of the season.*

**Ann and Jane Taylor's Poetry for Children.**

Containing:—THE ORIGINAL POEMS, HYMNS FOR INFANT MINDS, and RHYMES FOR THE NURSERY. With full-page and other Engravings. Crown 8vo, handsomely bound, cloth gilt, price 3s. 6d.

*In the task of writing for children no writers have been more eminently successful than the gifted sisters Ann and Jane Taylor, and the Publishers feel that they are doing a welcome act in issuing these charming productions in the present cheap and attractive form.*

### THE DAISY MAYFIELD SERIES.

In picture boards, price 3s. each; or cloth gilt, gilt edges, with coloured Frontispiece, price 5s.

1. **The Children's Story Book of Pictures, Poetry, and Music.** Full of beautiful Pictures, Pretty Stories, Songs for the Little Ones, Fairy Tales, Nursery Rhymes and Music.
2. **Merry Sunbeams.** A Pleasure Book for Boys and Girls, full of Tales and Stories, Children's Songs and Music, Amusements, Riddles, &c. With many Engravings.
3. **The Child's own Birthday Present Book.** Containing Stories and Tales for Children, Instructive Articles, Songs and Music, &c. With about 400 pictures.
4. **Golden Childhood, 1878.** The Children's Pleasure Book of Delight and Instruction, comprising Interesting Stories, Fairy Tales, Moral Tales, Nursery Rhymes (with music), Puzzles, &c. With about 400 pictures.

**Bible Steps for Little Pilgrims;** or Scripture Stories for Little Folks. With 16 Coloured Illustrations and 130 Engravings. 350 pages, large type, imperial 16mo, cloth gilt, 5s.

**Sacred Stories for Sunday Hours;** or, Scripture Narratives from the Old Testament. With 9 Coloured and 85 plain Illustrations. Imperial 16mo, cloth gilt, 3s. 6d.

**The Good Shepherd;** or, The Story of Jesus and His Apostles, for the Young. With Coloured and other Illustrations. Imperial 16mo, cloth gilt, 2s. 6d.

London: WARD, LOCK and Co., Warwick House, Salisbury Square, E.C.

WARD AND LOCK'S

## JUVENILE PUBLICATIONS.

- The Sunny Home.** The Story of a United Family. Being the First Volume of "THE CHILDREN'S PICTURE ANNUAL." By MERCIE SUNSHINE. With numerous Illustrations. Imperial 16mo, picture boards, 1s. ; cloth gilt, 2s.
- The Children's Picture Annual.** The Story of a United Family. (Second Series). By MERCIE SUNSHINE. With numerous Illustrations. Imperial 16mo, picture boards, 1s. ; cloth gilt, 2s.
- Mercie Sunshine's Chats About Animals.** Written with the object of inculcating in the minds of Children the necessity of Kindness to all Animals, large or small. Dedicated, by permission to the RT. HON. THE BARONESS BURDETT COUTTS. With many Engravings. Imperial 16mo, picture boards, 1s. ; cloth gilt, 2s.
- Mercie Sunshine's Chats About Birds.** Uniform with and forming a Companion Volume to "Chats about Animals." With many Engravings. Imperial 16mo, picture boards, 1s. ; cloth gilt, 2s.
- Nursery Rhymes, Old and New.** A Collection of the most favourite Nursery Rhymes, Jingles, and Stories. Numerous Illustrations. Picture boards 3s. 6d.
- Nursery Songs and Ballads.** With Eight Coloured Plates and numerous plain Illustrations. Picture boards, 3s. 6d., cloth gilt, red edges, 5s.
- Nursery Tales and Stories.** Uniform with above. Eight Coloured Plates and numerous plain Illustrations. Picture boards, 3s. 6d.
- The Book of Brave Old Ballads.** With 16 Coloured Illustrations, from designs by JOHN GILBERT. Picture boards, 3s. 6d.
- Moral Nursery Tales for Children.** By the Author of "The Golden Harp." With numerous Illustrations. Picture boards, 3s. 6d.
- The Child's Own Book of Country Pleasures.** With 16 Coloured Pictures and many Engravings. Picture boards, 3s. 6d.
- Domestic Animals and their Habits.** With descriptive Text intended to serve as an Introduction to Natural History. By H. W. DULCKEN, Ph. D. With 12 large double-page Coloured Illustrations of Domestic Animals and Familiar Birds, drawn from Nature. Fcap. folio, cloth gilt, 7s. 6d. ; wrapper boards, 6s.
- Wild Animals and their Homes.** With descriptive Text intended to serve as a first Introduction to Natural History. By H. W. DULCKEN, Ph. D. With 12 large double-page Coloured Illustrations of Wild Animals, drawn from Nature. Fcap. folio, cloth gilt, 7s. 6d. ; wrapper boards, 6s.
- Aunt Fanny's Nursery Tales and Rhymes.** With full-page Illustrations printed in Colours. Cloth gilt, 3s. 6d. ; or mounted on linen, 5s.
- Aunt Fanny's Picture Present Book.** With many Illustrations printed in Colours. Cloth gilt, 5s.
- Aunt Fanny's Pretty Picture Book.** With full-page Illustrations printed in Colours. Cloth gilt, 3s. 6d. ; or mounted on linen, 5s.
- Children's Pictorial Museum of Birds, Beasts, and Fishes.** With 16 Coloured Plates by HARRISON WEIR, and 200 Engravings in the text. Folio, picture boards, 5s.
- Child's Own Book of Scripture Pictures, Old Testament.** With over 100 Illustrations. Folio, wrapper boards, 5s.
- Child's Own Book of Scripture Pictures, New Testament.** With over 100 Illustrations. Folio, wrapper boards, 5s.
- The Child's Famous Picture Book.** With over 400 Pictures. The Cheapest Picture Book ever published. Picture boards, 3s.
- The Child's Wonder Picture Book.** With Hundreds of Illustrations. Uniform with "The Child's Famous Picture Book." Boards, price 3s.
- The Animal Picture Book for Kind Little People.** With large Coloured Pictures. Cloth, 3s. 6d.
- The Book of Animals.** With 9 Coloured Illustrations by HARRISON WEIR, and many Engravings. Cloth, 3s. 6d.
- Papa's Pretty Gift Book for All Good Little Boys and Girls.** With 150 Illustrations. Boards, 3s. 6d.

London ; WARD, LOCK and Co., Warwick House, Salisbury Square, E.C.



Digitized by



**ASSOCIATION  
FOR  
PRESERVATION  
TECHNOLOGY,  
INTERNATIONAL**  
[www.apti.org](http://www.apti.org)


**BUILDING  
TECHNOLOGY  
HERITAGE  
LIBRARY**

<https://archive.org/details/buildingtechnologyheritagelibrary>

**From the collection of:**

**INTERNATIONAL MASONRY INSTITUTE**








THE  
ILLUSTRATED  
ARCHITECTURAL, ENGINEERING, & MECHANICAL  
DRAWING-BOOK.

FOR THE USE OF  
Schools, Students, and Artisans.

---

UPWARDS OF 300 ILLUSTRATIONS

---



BY ROBERT SCOTT BURN,

AUTHOR OF "THE ILLUSTRATED DRAWING-BOOK," "MECHANICS AND MECHANISM," "ORNAMENTAL AND ARCHITECTURAL DESIGN," "THE STEAM ENGINE, ITS HISTORY AND MECHANISM," ETC.

THIRTY-SECOND THOUSAND.

LONDON:  
WARD, LOCK, AND CO.,  
WARWICK HOUSE, SALISBURY SQUARE

**UNIFORM WITH THIS VOLUME.**

*Price 2s. each.*

**THE ILLUSTRATED DRAWING BOOK.**

Comprising Pencil Drawing, Figure and Art Perspective, Engraving, &c. With 300 Illustrative Drawings and Diagrams.

**THE STEAM ENGINE:**

Its History and Mechanism. With 310 Illustrations.

**MECHANICS AND MECHANISM.**

Elementary Essays and Examples. With 250 Illustrations.

**ORNAMENTAL DRAWING & ARCHITECTURAL DESIGN.**

With Notes, Historical and Practical. With 300 Illustrations.

---

LONDON: WARD, LOCK, & CO., SALISBURY SQUARE, E.C.



THE  
ILLUSTRATED  
Architectural, Engineering, and Mechanical  
DRAWING-BOOK.

---

INTRODUCTION.

IN the work on *Practical Geometry*, in the Series of Educational Books of which this treatise forms a part, we have given simple definitions and constructions of the various forms and figures which may be said to constitute the foundation of all drawing. We have there endeavoured to show that a knowledge of geometrical construction is necessary, before a thorough appreciation of the principles of outline sketching can be obtained, and a ready facility acquired in performing its operations. However much this position may be controverted as regards its application to an art which is generally looked upon as independent of, rather than dependent on, strict and formal rules, there can be no doubt, we think, that it holds with all completeness in reference to that which it is now our duty to illustrate and describe. In fact, so much do the various branches treated of in the following pages depend upon a knowledge of geometry, that many class them under the generic title of "geometrical drawing." Those commencing the study of these arts—so useful to the architect and the mechanic—without this knowledge of geometry, will be disappointed as to their speedy proficiency, and will labour under great disadvantages, from not understanding the principles upon which the constructions are founded.

In carrying out the objects of the present work, we purpose strictly to adhere to the plan followed in *The Illustrated Drawing-Book*, of adopting a series of progressive lessons, leading the pupil from the consideration of simple examples up to those more complicated in their construction. So that the simple steps are well understood, the more difficult ones will be easily mastered by the pupil who attends to the various gradations of examples. We have endeavoured, as far as the discursive

nature of the subject has admitted, to preserve a distinct classification of objects, and a unity in the examples, so as to make the pupil thoroughly conversant with one department before proceeding to the consideration of another. Where this has been departed from, and an apparent mixing up of examples has resulted, considerations involving obvious advantages have suggested the change. On the whole, however, we trust that the classification so desirable has in some measure been obtained.

Although aware that architectural and mechanical drawing has for some time taken its place in many scholastic establishments as a branch of ordinary education, we are nevertheless anxious to see it still more extensively adopted. We conceive it likely to be of more general use—even to those who may not at all contemplate following up any of the professions to which it is more specially useful—than may at first sight be acknowledged. Apart from the habit of method, which, if it does not create, it will at least foster and encourage, we see many advantages accruing to those desirous of having a knowledge of science by an acquaintance with its practice. And there are few, we think, in these days of practical science, who are not likely to be interested in its progress. Geometrical drawing—taking the term in its widest sense—is an art which will enable those acquainted with its principles to understand a scientific exposition with greater readiness than those can do who are ignorant of it. To convince the reader of the truth of this, we have only to remind him, that few expositions of improvements or inventions in practical science, in its widest range, are ever made without the aid of sketches,—these ranging from the simple diagram up to the more complicated drawing; and the ready understanding of these is open only to those acquainted with drawing. This consideration should, we think, weigh very forcibly with those who are doubtful of the propriety of following the example of so many educational establishments, in introducing geometrical drawing as an ordinary branch of education. To those desirous of following out the profession of architect, engineer, or mechanic, an acquaintance with the art is as indispensable as a knowledge of sketching from nature or objects is to the artist or painter. Without it, the practical man, however ingenious, will inevitably fail in perfecting, unaided, his ideas with that facility available to the accomplished draughtsman. Its usefulness in the workshop, moreover, is no less conspicuous than in the study or bureau, in enabling the inventor or improver to communicate his ideas clearly and readily to the workman. To the latter also it is equally important and indispensable,—we mean to those who are desirous of raising themselves above the level of the mere operative, the handler of the hammer or the mallet. In short, to him who, in the exercise of his important avocations as architect or engineer, wishes to render himself independent of extraneous assistance in planning and working out his original



ideas, and capable of communicating their results to others with facility, a knowledge of the art is absolutely indispensable. To those who have at all considered the subject, further comment on its value to the practical man is altogether unnecessary.

One cause probably of the art not being so generally adopted in educational establishments, is the extreme paucity of books treating exclusively on the subject; and of those calculated to serve as guides, the price is nearly prohibitive, at least to the generality of purchasers. A work taking up all the departments of the subject, treating them *methodically* and *fully*, yet issued at a price absolutely within the reach of all, has long been a desideratum; which we venture to hope the present volume may possess some claim to having supplied. As to its *method*, we have followed the same plan which, adopted in the *Illustrated Drawing-Book*, met with a considerable amount of success. If we have failed to attain in this the same clearness of exposition and attractiveness of illustration, this may be attributed, in some degree, to the nature of its subjects, which are not in themselves so attractive as those contained in the above work. At all events, we may lay claim to a strong desire to make it, in all its departments, as attractive and useful as possible. As respects the *fulness* or completeness of the work, a mere glance at its pages will show that, even should fault be found with the method of the lessons, none can be alleged on the score of the meagreness of their illustrations. The present volume is strictly a "drawing-book," showing how drawings—whether architectural, engineering, or mechanical—may be copied and laid down. The æsthetic principles and technical rules which *dictate* the proportions, the style, and the methods of planning structures—whether these be architectural or mechanical—are not treated upon, excepting in some few instances. These rules and principles, we conceive, belong to more strictly professional treatises. A work which is contemplated in this series—on "Ornamental and Architectural Design"—will, in one department, provide a guide to the pupil, desirous of going into the principles of one art, of which we here give lessons useful in delineating its examples. A work giving a clear exposition of the principles and practice of the other departments, namely, "Civil and Mechanical Engineering," is yet a desideratum among educational books. Should it be thought advisable, such a treatise may probably be included in the present series.

R. S. B.

## PREFACE TO THE SECOND EDITION.

---

THE Author feels gratified that the demand for another Edition of this Work has enabled him, by a careful revisal of every example, to render the description by which it is elucidated as clear and explicit as possible, and to expunge many errors and crudities which encumbered the first issue. Various improvements in the plan of the book have been suggested to him, some of which he has endeavoured to embody in the present issue. The majority of these, however, are more intimately connected with the department of a work to which frequent reference is made in this volume, namely, that on "Ornamental and Architectural Design," and the utility of which is adverted to in the Introduction above given. This work was suggested to the Author during the preparation of the present volume, some years ago; and since that period he has had numerous evidences afforded him of its probable utility in an educational course. From these the work is considered a desideratum, which it is deemed desirable to supply. For this purpose, the Publishers of the present volume have kindly entrusted its preparation to the Author; and it is hoped that in a short time it will be ready for publication. The treatise is intended to embody a variety of examples in the different styles of *Ornamentation*, and of the methods by which they are drawn; together with notes, historical, æsthetical, and practical, on *Architectural Design*; the whole having an immediate aim to their application to the general purposes of utility, as well as being calculated to afford a variety of useful information to the general reader.

R. S. B.



THE  
ILLUSTRATED  
Architectural, Engineering, and Mechanical  
DRAWING BOOK.

ARCHITECTURAL DRAWING.

In this department the first lessons will be those which require for their construction nothing but the arrangement and combination of right or straight lines. It is scarcely necessary here to state, that the instruments requisite for the various operations are the same as those required for the constructions described in the *Illustrated Practical Geometry*, the 'drawing-board,' 'square,' and 'triangle,' these being absolutely indispensable. As this work is strictly designed to be a sequel to that on Geometry, we beg to refer the reader thereto for a description of these, and the readiest methods of using them.

EXAMPLE 1. To draw the portion of 'hipped roof' shown in fig. 1.




fig 1

On the drawing-paper, properly fastened to the board, mark any point *a*; parallel to the side of the drawing-board, draw from this point any line, and make it equal to *ab*. Bisect this in the point *m*; at right angles to *ab* draw from this point a line to *e*, and make this equal to *me* in the copy. Join *ea*, *eb*. At right angles to *ab*, from these points draw to *cd*, making the length of these equal to *bc* in the copy. Draw the lines *cc*, *dd*, parallel to *ab*. The example given in fig. 1 will thus be copied. The pupil should be very careful to take the measurements in his 'compasses,' or 'dividers,' equal to those in the copy.

EXAMPLE 2. To draw the part plan of the wall of a house, showing the projection of one side of fireplace, with the internal flue, in fig. 2. Divide the thickness of the wall *g'g* by the centre line *ab*, bisect *fe*, and draw at





proceeded with the copy as directed above, the produced lines being marked in light pencil lines, the first operation is to draw any line, as  $a b$ , on the most convenient part of the paper on the board on which the drawing is to be copied. From  $a$  measure to  $b$ ; and from these points, at right angles to  $a b$ , draw lines to  $c$  and  $d$ ; make  $b c$ ,  $a d$ , equal to the corresponding lines in the copy; join  $d c$ . Next take from the copy the measurement from  $d$  to  $e$  (the point found by producing  $h f$ ), and lay it from the point  $d$  in the board on the line  $d c$ . Do the same from  $c$  to  $e$ ; parallel to  $b c$  draw lines  $e h$ ,  $e h$ ; measure next the distance from  $d$  to  $o$ , and transfer it on  $a d$ ,  $b c$ , to  $o o$ ; parallel to  $a b$  draw a line  $o o$ . From  $g$  and  $f$  measure to  $h h$ ; transfer these, and from the points obtained draw a line  $h h$  parallel to  $o o$ . With distance  $h s$ , or  $n f$ , measure from  $h$  to  $s$ , from  $g$  to  $m$ , from  $n$  to  $f$ , and from  $t$  to  $h$ ; join the points. In inking the lines, the points  $b c$ ,  $d a$ ,  $h g$ ,  $s m$ ,  $t n$ ,  $h f$ , will be their terminations. In the examples given in the figures the lines not dotted show the complete design.

EXAMPLE 4. To draw the outlines of an ordinary sash window. Make any line  $c d$  on the paper on the board equal to the corresponding line in the copy, fig. 4. At the points  $c d$  draw lines perpendicular to  $c d$  of an indefinite length. With the measurement  $c a$ , from the copy, cut the lines  $c a$ ,  $d b$ , in  $a, b$ ; join  $a b$ . Divide the line  $c d$  into three equal parts in the points  $n, n$ ; parallel to  $a c$ , from these draw lines meeting  $a b$ . Divide the line  $a c$  into four equal parts in the points  $m, e, g$ ; parallel to  $a b$ , from these draw lines meeting  $b d$  in  $m', f, h$ . The parallelogram  $a b d c$  is divided into twelve lesser ones, representing each a pane of glass.




fig. 4.




fig. 5.

EXAMPLE 5. To draw the diagonal lines representing the panes in a rustic window, fig. 5. Draw  $c d$ , making it equal to  $c d$  in the copy;  $c d$  is the side of the square  $a b d c$ , which describe. Divide the sides  $c d$ ,  $a c$ , each into six equal parts; join the corresponding points, as 1, 2, 4, 5, 3, 6.

EXAMPLE 6. To draw the central pilaster in fig. 6. Divide in the copy the line  $a b$  into two equal parts at  $e$ , and through this, at right angles to  $a b$ , draw the line  $c c$ ; bisect the part  $o o$  by a line  $s f s$ . On the paper on which the drawing is to be made, draw any line representing  $c c$ , and another at right angles to the first, representing  $a b$  in the copy, fig. 6. The intersection of these two lines will give the position of the point  $c$ . Take from the copy the measurement  $c f$ ; transfer it from  $c$  to  $f$ ; draw parallel to  $a b$  through this point a line, representing the line  $s f s$  in the copy. With  $a c$

from *c* lay off on *ab* to *a*, *b*; draw indefinite lines from these points perpendicular to *ab*; measure *ad*, *be* equal to *ad* in the copy; join *ed*. With measurement *ft*, lay off from *f* to *t* and *u*, and on the line *cc* as many times as necessary; through these several points draw lines parallel to *ab*; these will be the centre lines of the parts corresponding to *oo*. With *af* from the points of intersection of these with the line *cc*, lay off equal to *oo*; through the points draw lines parallel to *ab*; produce *ab* to *gg*. The terminations of the parts equal to *oo* will thus be formed, as represented in fig. 6. In the copy, as in fig. 4, produce the internal lines *hh*, to meet the line *ab* in *mn*; from *c*, with *cm* lay off on *ab* to *m*, *n*, and parallel to *cc* from these points, draw lines *mh*, *nh*. These lines will terminate the alternate internal portions. Another method of copying this figure will be as follows:—Draw any line *ab*, and at right angles to it another, *bg*; the point where they meet will correspond to the point *b* in the copy, and thus a datum point will be obtained from which to take measurements. With *ba* from the copy, set off *ab* parallel to *de*; from *a* draw *dg*; make *ad*, *be* each equal to the corresponding lines in the copy; join *de*. From *e* measure to the line above it, and transfer it to the paper on the board; from the same point measure to the next line; and so on in succession. Transfer these measurements to the corresponding points on the paper on the board, and through the points obtained draw lines parallel to *ab*; these will form the under and upper lines of the parts *oo*. The lines representing the boundary-lines of the alternate inner portions can be obtained by measuring from *e* or *d* to the lines as *mh*, *nh*, in the copy, and transferring them; thereafter through the points obtained drawing lines at the parts required parallel to *bg*.




fig. 6.




fig. 7.



**EXAMPLE 7.** *To draw the quoins of a house in fig. 7.* Produce in the copy the external line  $f$  to meet the base line  $ag$  produced in  $e$ ; next, on the paper on the board draw any lines  $ac$ ,  $ab$ , at right angles to each other; then the point of intersection will correspond to the point  $a$  in the copy. Measure the distance  $ag$  from the copy, and transfer it to the board; do the same with  $ae$ . From these points draw lines parallel to  $ab$ , as  $gh, fe$ . The line  $ab$  will represent the corner line of house, the line  $gh$  the internal line of quoins, and  $ef$  the external. Suppose  $ab$  to be the height on which the quoins are to be disposed, make  $ab$  on the board equal to  $ab$  in the copy; and on the supposition that there are to be twelve quoins in  $ab$ , divide  $ab$  into twelve equal portions, and through the points thus obtained draw lines parallel to  $ac$ , as  $bh, fd, 1s, 2t$ . Finish as in the copy. Another method is as follows:—Draw lines  $ac$ ,  $ab$  as before; measure from  $a$  to  $g$ , and draw from this a line parallel to  $ab$ ; measure from  $a$  to  $1$ , and draw through the point a line  $1s$ ; measure  $1s$ , transfer it to the paper on the board; measure  $st$ , and draw it at right angles to  $ae$ ; join  $t2$  by a line parallel to  $ae$ . The first quoin  $1s, t2$  will then be drawn, and afford datum points from which to finish the others; thus the line  $st$  produced towards  $f$  will give the external line of all the others; and the distance  $a1$ , transferred in succession to the line  $ab$ , will mark the horizontal distances.

EXAMPLE 8. To draw the figure in fig. 8, which represents the plan of the roof of an outbuilding, or external addition, projecting from the main wall *f n s*. The dotted line *c d* must be first drawn in the copy, dividing




fig. 8.

$ab$  into two parts at  $c$ ; next, on the paper on the board draw any two lines at right angles corresponding to those in the copy, as  $cd$ ,  $fdns$ . To avoid unnecessary repetition, we wish the reader to understand that, when we give directions to measure any part or distance, as “measure from  $c$  to  $b$  and  $a$ ,” we mean that the distance  $cb$  is first to be taken from the copy in the figure, and transferred to the corresponding point on the





**EXAMPLE 10.** *To draw the window in fig. 10.* Bisect in the copy  $ab$  in  $c$ , and draw a line  $cf$ ; draw lines on the board corresponding to  $ab, cf$ . From  $c$  measure to  $a$  and  $b$ , and draw lines  $ae, be$ . From  $c$  measure to  $n$ ,  $d, m, s, h$ , and  $f$ , and through all these points draw lines parallel to  $ab$ ,—that drawn through  $d$  deciding the length of the lines  $ee$ . From  $n$  measure to  $nn$ , a distance equal to half  $nn$  in the copy. Do the same at the points  $f$  and  $m$  to  $mm, gg$ . Parallel to  $fc$  from  $n, n$  draw to  $i, i$ , and join  $hi, hi$ . From  $g, g$  parallel to  $cf$  draw to  $m, m$ . From  $d$  lay off to  $oo$ , and from these draw lines to  $m, m$ , parallel to  $cf$ , meeting the line  $mm$ ; join these with the point  $s$  by lines parallel to  $hi, hi$ . From  $i$  measure to  $k$ , and make  $kk$  at right angles to  $oi$ . At right angles to  $kk$  make  $kp$ ; from  $p$  measure to  $r$ , and draw  $rt$  parallel to  $kk$ . Measure  $tx$ , and put in the line  $11$ .




fig. 10.




fig. 11.

**EXAMPLE 11.** *To draw the window in fig. 11.* Bisect  $ab$  in  $c$  in the copy, and draw  $cd$ . On the board draw any two lines corresponding to  $ab, cd$  in the copy; measure from  $c$  to  $a$  and  $b$ , and draw from these points to  $gg$  lines parallel to  $cd$ ; measure to  $gg$ , and join  $gg, gg$ . From  $c$  measure to  $e$  and  $d$  and  $f$ ; through these draw lines parallel to  $ab$ . From  $f$  measure to  $ff$ , and from  $e$  to  $ee$ ; join  $fe, fe$  by lines parallel to  $cd$ . From  $e$  measure to  $h, h$  and to  $n, n$ ; from  $d$  measure to  $m, m$ , and join  $mn, mn$ . From  $hh$  parallel to  $cd$  draw lines to  $oo$ ; measure  $ho$ , and parallel to  $hh$  draw lines from  $oo$  meeting  $mn, mn$ . Draw the parallelogram within  $ee, ff$ , and from  $c$  measure to  $s$  and  $t$ , and through these draw lines parallel to  $ab$ ; these represent the divisions of the glass. Put in the lines  $11$  parallel to  $cd$ , joining  $gg, hh$ : the drawing is complete.

**EXAMPLE 12.** *To draw the form of window in fig. 12.* Draw the centre-line  $cc$ , as in preceding examples. Corresponding to the lines  $ab, cc$  draw



two on the board. From  $c$  measure to  $ab$ , and from the same point to  $f$ ,  $m$ , and  $c$ ; through  $c$  draw a line parallel to  $ab$ , as  $ee$ , and through  $f$ ,  $ff$ , and  $m$ ,  $gg$ . Measure from  $f$  to  $f$ , and from  $m$  to  $g$ ; join  $gf$ ,  $gf$ . From  $c$  measure to  $x$ , and join  $gx$ ,  $gx$ . Parallel to  $ab$  put in the lines  $dd$ ,  $hv$ ,  $hv$ . From  $v$ ,  $h$ , parallel to  $gf$ , draw lines to meet  $g$ ,  $g$ , and from the points  $o$ ,  $o$  lines to meet these, parallel to  $gx$ . From  $e$  measure to  $n$ , and put in  $nt$ ,  $nt$ ; put in the square  $ssss$  by lines parallel to  $mo$ ,  $gx$ . Draw the external 'dressings' by the method described in fig. 10.




fig. 12.




fig. 13.

**EXAMPLE 13.** To draw the chimney-shaft in fig. 13. Bisect the line  $ab$ , draw a line  $d o c$  through this; draw corresponding lines to  $ab$ ,  $cd$  on the board; measure from  $c$  to  $o$ ,  $s$ ,  $x$ , and  $h h$ ; measure from  $o$  to  $g g$ , and put in the part  $g g$ , as well as those receding parts under it. Through  $s$  draw a dotted or *occult* line\*  $e s e$ , divide  $o g$ ,  $o g$  into two parts at  $p p$ , with the half of  $o p$ , from  $s$  lay off four times to  $e e$ , on both sides of the line  $c d$ , join  $g e$ , and from  $t$ ,  $t$  lines meeting  $f f$ . Produce the lines  $e p t$  and  $s$  beyond the line  $h h$ ; measure from  $l$  to  $n$ , join  $n m$ ,  $n m$ ,  $v x$ , and  $x l$ , and put in the remaining portion as by preceding lessons.

**EXAMPLE 14.** To draw the steps of a staircase as in fig. 14. Let  $d g$  be the height from one line of floor to the other, represented by the upper and under lines; and  $c d$  the distance in which the steps are to fall. The height of each step is 7 inches, technically called a 'riser;' the breadth being usually 9 inches; this part on which the foot rests is called the 'tread.' The measurements in the figure are taken from a scale one-fourth of an inch to the foot. Suppose the width  $c d$  to be 6 feet, allowing 9 inches for the tread, this will give eight divisions; divide  $c d$  therefore into eight equal parts, and from these points draw lines perpendicular to  $c d$ . Taking the

\* For definition of the various kinds of lines see *Illustrated Practical Geometry*.



height  $dg$ , from one landing to another, to be 5 feet 3 inches, this will give nine divisions of 7 inches each; divide  $dg$ , therefore, into nine equal parts, and from the points thus obtained draw lines parallel to  $cd$ . From the intersection of the line 1 on  $cd$ , and 1 on  $ab$  at  $a$ , draw to the point of intersection of 2 the line from 1, with that from 2 on  $dg$ ; from the point  $n$ , the intersection of the lines 22, draw a line meeting the intersection of the vertical line 2 with the horizontal 3. The intersection of the lines 33 gives the point of next step, and so on, each time proceeding nearer the line  $ag$ .




fig. 14.

EXAMPLE 15. To delineate the plan of the stairs in the preceding lesson. The distance  $ab$ , fig. 15, corresponds to  $dg$  in fig. 14; the breadth  $ab$  being that between the side walls or balustrades. The height  $ab$  is divided into 9 equal parts, each part representing a step. If a line be drawn from the point 9, fig. 14, to the left-hand top corner of the front step at  $c$ , it will be found to touch the corners of all the steps; this forms the foundation for another method of delineating the profile of the steps in a staircase, as described in

EXAMPLE 16. Let 12, fig. 16, be the breadth, and  $2b$  the height from one landing to another, as before; draw the line 13, and join  $b3$ . From  $b$  on the perpendicular  $b2$ , make off to  $c$  a distance equal to the height of one




fig. 15.




fig. 16.

riser equal to  $a13$ . From  $c$  draw a line exactly parallel to  $a2$ , or perpendicular to  $b2$ , meeting the diagonal line  $b3$  in  $d$ ; from  $d$  drop a perpendicular  $de$ , equal 7 inches, or  $bce$ ; from  $e$  draw parallel to  $cd$  a line meeting  $b3$  as before; from  $f$  drop a perpendicular to  $h$ , and proceed thus till finished. Great care must be taken to draw the lines truly parallel to the proper lines; also to drop the perpendiculars, as  $de$ , exactly from the point where the horizontal lines, as  $cd$ , join the diagonal  $b3$ . The least deviation from accuracy in the beginning will inevitably result in throwing the operations towards the end far wrong. The lines should be drawn very finely, so that the exact points of intersection will be easily observable. The

method shown in fig. 14 will be least liable to error. We give the two methods, as affording opportunities of extended practice to the pupil, and as suggestive of plans he may himself adopt.




fig. 17.

EXAMPLE 17. To delineate the plan of a staircase having 'returns,' by which the direction of the steps is changed. Assume any point in fig. 17, as *a*; draw *ab*; perpendicular to it draw *ac*. Measure from *a* to *e* and *g*, draw from these points *ef*, *gh* parallel to *ac*; from *a* measure to *d*, and draw *dm* parallel to *ab*; measure from *d* to *c*, and draw the line 1; divide *dc* into seven equal parts. From *d* measure to *n*, and from *a* to *o*; join *sn*, *so*. We give another lesson similar to this in

EXAMPLE 18. Draw *ab*, *bd* at right angles to one another; from *b* measure to *c* and *e*, and draw *eh*, *ch* at right angles to *bd*, *ba*. Divide *ed* into two equal parts, and *ca* into seven. Measure from *c* to *f*, and from *b* to *g*; join *hf*, *hg*.

EXAMPLE 19 shows plan of cellar-steps having a return at head which is entered from *p*, and another at foot entered from *s*. A party-wall is between the two houses, the steps of the adjoining house being shown in dotted lines.




fig. 18.




fig. 19.

Draw *ac*, *ab* at right angles; from *a* measure to *c*; draw *cd*, representing the inside line of external wall, parallel to *ab*. From *a* and *c* measure off the thickness of party-wall, dividing the two staircases, and draw a line *db* parallel to *ac*. From *d* and *b* measure to *e* and *f*; from these points draw lines parallel to *ab*. From *c* measure to *m*, and from *a* to *n*; join *em*, *nf*. Measure from *d* to *h*, and from *b* to *g*; join *fg*, *eh*. Divide the distance between *ef* into as many equal parts as in the drawing; from these points draw lines parallel to *ab*; these represent the steps in the stair parallel to the party-wall.

EXAMPLE 20. In fig. 20 we give a sectional vertical sketch, showing a flight of stairs *c*, reaching to the first landing-place *d'*, from the ground-floor *a b*, with return steps *e*, leading to the first-floor *f*; the landing-place *d*, counts as one step, a step *d'*, rising into the room of which *d'd* is the door; *a a* is the door of a room on the ground-floor, *g g* of one on the first-floor. The ground-plan of this is shown in




fig. 20.

EXAMPLE 21, fig. 21, the letters of reference in which correspond with those of fig. 20. The first flight, *c c*, is drawn in full lines, the return being dotted. The chamber or first-floor plan is shown in

EXAMPLE 22, fig. 22. The steps of the first flight are shown in full to where the landing reaches and the banisters begin; the dotted lines represent the steps, which are hid by the flooring-boards of the chamber floor.




fig. 21.




fig. 22.

We now proceed to the consideration of lessons in which a combination of straight and circular lines are met with. The first lesson is given in

EXAMPLE 23, fig. 23. Let *a b* be the ground-line of a house, and with part of the circular-headed window of apartment in basement seen above it; divide the width into two equal parts at *c*, draw *c d* perpendicular to *a b*.






fig. 23.

Draw lines on the board corresponding to  $ab$ ,  $cd$ ; the centre of the curve will be found somewhere on the line  $de$ . By trial on the copy, it will be found to be at  $e$ ; measure from  $c$  to  $e$ , and from  $e$  as centre, with  $ed$  as radius, draw the curve, joining the short perpendicular lines from  $ab$ . The centre from which the part of the circle in the copy is described can easily be found by adopting any of the methods described in *Prac-*

*tical Geometry*, one of which is here shown in fig. 25.

EXAMPLE 24. To draw the circular-headed fire-place in fig. 24. Let  $ab$  be the width, bisect it in  $c$ , draw  $cd$  perpendicular to  $ab$ ; draw corresponding lines to  $ab$ ,  $cd$  on the board; measure from  $c$  to  $a$ ,  $b$ , from these draw lines perpendicular to  $ab$ , and equal to  $af$ . From  $c$  as a centre, with  $cf$  as radius, describe the arch  $fde$ . Measure from  $a$  and  $b$  to  $h$ ,  $h$  to get the width of jambs, and perpendicular to  $ab$  draw  $hm$ ,  $hm$ ; measure to  $m$ , and draw  $mn$  parallel to  $ab$ ; measure to  $o$ , and parallel to  $cd$  draw lines  $oo$ ,  $oo$ .




fig. 24.




fig. 25.

EXAMPLE 25. To draw the circular-headed window in fig. 25. Let  $ab$  be the width, bisect it in  $c$ , draw  $cg$  perpendicular to  $ab$ . From  $a$ ,  $b$  parallel to  $cg$  draw lines to  $d$  and  $e$ , the termination of the curve. To find the centre from which the curve  $dfe$  is described, take any points  $e'$  and  $f$  in the copy, and from these points, with radius greater than half the distance between them, describe arcs cutting in  $g$ ,  $h$ . From  $d$  and  $e'$  in like manner



**EXAMPLE 27.** *To draw the walls and cellar-flues given in fig. 27.* In the copy continue the line  $d$  across  $a$ , the line  $g g$  across  $f$ ,  $t t$  across  $m$ . By trial find the centres of the circles  $p, p$ , join them by a line  $p o p$ . On the board draw any line  $a b$ , representing the centre line of the wall  $f m$ , and at right angles to it another  $d d$ . From  $a$  measure to  $e$  and  $c$ , from these draw lines forming a parallelogram, as in the copy. From  $a$  measure to  $f$ , and through  $f$  draw a line parallel to  $d d$ ; from  $f$  measure to  $g g$ , put in  $h, h$ , and join  $g, h$  by lines perpendicular to  $g g$ . From  $a$  measure to  $o$ ; draw a line




fig. 27.

through this parallel to  $d d$ ; from  $o$  measure to  $p p$ ; these points are the centres of the circles. From  $a$  measure to  $m$ ; draw a line as before, and measure to  $s, s$ . From  $m$  measure to  $t, t$ , and draw lines to  $1, 2$ ; put in the thickness of the wall  $m f$ .

**EXAMPLE 28.** *To draw the 'bull's eye' in fig. 28.* Bisect  $ee$  in  $d$ ,  $ff$  in  $d$ , and from these draw lines intersecting at  $a$ . On the board draw lines corresponding to these. From  $a$ , with  $ah$  as radius, describe the circle  $ah$ . From  $a$  measure on the four radial lines to  $dd$ , from  $d$  measure to  $e, e$ , &c.; join  $ede$ . From the points where the circle  $ah$  cuts these lines, measure from  $h$  to  $m$ ; join  $f m$ ; do this at all the radial lines. From  $a$ , with  $as$  as radius, describe the parts of a circle joining the key-stones, as  $tt$ , &c. From  $a$ , with  $ah$ , describe in like manner a circle, as  $mo$ . From  $a$  measure to  $c, c$ , and from  $c$  to  $b$ ; from  $a$ , with radius  $ab$ , describe parts of a circle, joining both ends of the lines  $c, c$ ; finish as in the sketch.




fig. 28.



**EXAMPLE 29.** To draw the bracket of a cornice in fig. 29. Let  $aa$  be the line of wall; from  $a$  draw  $ab$  perpendicular to  $aa$ . Measure from  $b$  to  $c$ , and draw  $bc$ . Measure from  $a$  to the point 5, and draw from it a short line




fig. 29.




fig. 30.

perpendicular to  $aa$ , as in the diagram. From  $a$  to 1; from these draw indefinite lines. Measure from  $b$  to 2, and from  $aa$  to 1; from these draw indefinite lines. Measure from 5 to  $e$ . Measure from the line  $bc$  to the point 3. By trial find the centre of the circle  $ce$  in the copy, as  $d$ , and transfer it to the board; join by an arc  $ee$ .

**EXAMPLE 30.** To draw another form of bracket-cornice. Draw a line  $ab$ , put in the part  $ad$  1. Draw  $cd$  parallel to  $ab$ . From  $a$  measure to  $b$ , and from  $d$  to  $c$ . By drawing a line exactly through these points, the angle of the line of roof  $ecb$  will be obtained. From  $c$  measure to  $e$ ; by trial find in the copy the centre from which the curve  $ed$  is described, as  $m$ ; with the radius thus found, from the points  $d$  and  $e$  on the board, describe arcs cutting in  $m$ ; with same distance still in the compasses, from this point describe a curve joining  $de$ . From  $d$  and  $e$  measure to  $h$ , and put the other arcs in as shown.

**EXAMPLE 31.** To draw the window in fig. 31. Draw two lines,  $ab$ ,  $cd$  at right angles to one another, intersecting in the point  $c$ . Measure from  $c$  to  $a$  and  $b$ , and also to  $d$ ; through  $d$  draw a line  $ede$  parallel to  $ab$ ; measure from  $d$  to  $e$ ; join  $ae$ ,  $be$ . Measure from  $c$




fig. 31.

to  $m$ , and draw through this a line parallel to  $ab$ ; measure also to  $n$ , and draw  $nn$ . From  $m$  measure on both sides the distance  $mo$ ;  $mn$  also from  $n$  to  $n$ ; these points are the centres of the circles shown in the sketch, the method of putting in of which is still further elucidated by

EXAMPLE 32. Let the line  $cd$ , fig. 32, correspond to  $omn$  in fig. 31,  $ab$  to  $nm$ , and  $fe$  to  $nn$ . From the point of intersection of these lines with  $cd$ , describe the circles as in the drawing. On each side of  $cd$  draw the




fig. 32.

lines  $m, m$ ; and parallel to same lines, lines  $s, s$  touching the circles. From  $fe, ab$ , lay off to  $nn$  lines equal to  $m$ ; and from  $m$ , to  $ss$  equal to the distance of the line  $ms$  from  $cd$ ; join  $ps$  and the points corresponding.

EXAMPLE 33. To draw the basement arch below the principal entrance to a house, as in fig. 33. Draw the line  $ab$ , and at right angles to it a line from  $c$ , the centre of  $ab$ . Measure from  $c$  to  $a$  and  $b$ . From same point,




fig. 33.

with  $cf$  as radius, describe the semicircle  $ff$ . From  $c$  measure to  $d$ , draw a line through this parallel to  $ab$ . Measure from  $d$  to  $e, e$ ; join  $ae, be$ ; put in the key-stone  $dg$ . Divide  $be$  into five equal parts, and from these points, parallel to  $ab$ , draw lines through  $dc$  to the line  $ae$ . From  $s$  measure to  $t$ , and draw lines on each side the key-stone  $dg$ , parallel to its sides. From  $t$  measure to  $k$ . Divide  $kf$  into five equal parts. From  $i$  measure to  $h$ ; from  $c$ , with  $ch$ , describe a dotted semicircle passing through the points  $nn, h, m, m$ ; this will give the termination of the lines drawn from the points on  $be$ . Join these with lines to the points found in the part of the circle  $kf$ .







measure to  $d$ , and draw  $f d f$  parallel to  $a b$ . From  $d$  measure to  $e e$  and  $f f$ ; from  $e$  measure to  $g$ , and from  $g$ , with  $g h$ , describe the quadrant  $h m$ . From  $m$  draw  $m i$  parallel to  $c d$ ; from  $f$ , with radius  $f n$ , describe the arc meeting the line  $i$ . Finish as in the part to the left of the sketch.

EXAMPLE 38. To describe the flutes and fillets in fig. 38. Let  $a b$  be the diameter of column, bisect it in  $c$ ; draw  $c d$ . Draw on the board lines corresponding to these, and from the point  $c$ , with  $c b$ , describe the semicircle  $a d b$ , representing half of the column. Bisect the quadrant  $a d$  in the point




fig. 38.

$e$ , and divide the arcs  $a e$ ,  $e d$ , by points  $g, f, h, m$ . Mark the position of these by radial lines from  $c$ , as in the copy. Divide the part  $a g$  into eight equal parts; and with three of these as radius, from the points in the quadrant, as  $g, f$ , &c., describe semicircles. Six parts will thus be given to each flute, and two to each fillet: and the column will have twenty-four flutes.

EXAMPLE 39. To describe the flutes in a Doric column without the fillets, as in fig. 39. Proceed, as in last example, by dividing the quadrant  $b e c$  into




fig. 39.

six equal parts, as  $e, m, n$ , &c., giving to the entire column twenty-four flutes as before. Draw radial lines from  $b$ . Divide  $af$  into four equal parts, and lay one of these on  $ab$  produced to  $e$ ; from  $b$ , with  $be$ , describe a semicircle as  $em n$ , cutting the radial lines. Bisect  $af$  in  $o$ , and with  $fo$  as radius, from the points—where the dotted semicircle intersects the radial lines—as centres, describe the arcs as in the copy. Another method is shown in

EXAMPLE 40, fig. 40. Describe a semicircle  $ade$ , and divide the quadrant  $b a d$  into five equal parts, so as to give twenty flutes to the column. Produce  $ab$  to  $f$ ; bisect  $ae$  in  $h$ , and from  $e$  lay off  $eh$  to  $m$ ; join  $hm$ , and




fig. 40.

with distance  $he$  lay off on the radial line  $be$  to  $n$ . From  $b$ , with  $bn$ , describe the dotted semicircle,  $fn o$ . The centres of the flutes are placed where the radial lines intersect this semicircle. From  $n$ , with  $nm$ , describe the curve  $m h$ , and draw the others in the same manner.

EXAMPLE 41. To describe the flat flutes and fillets as in fig. 41. Describe the semicircle  $adc$ , and divide the quadrant  $b a d$  into six equal parts;




fig. 41.

divide  $ae$  into five equal parts. With two of these from the radial line, lay



off on each side, as  $f, h$ . With one part lay off from  $c$  to  $m$ , and from  $b$ , with  $b m$ , describe a semicircle  $c d a$ ; complete the diagram as shown. This will give the depth of the flutes, one; the width, four; and the width of fillets, one.

EXAMPLE 42. To describe the cabled moulding in fig. 42. Divide the semicircle  $a c d$  in the same proportion as in fig. 38, giving an equal number




fig. 42.

as in that example. From  $b$ , with  $b e$ , describe the semicircle  $e f f$ . From the points where the radial lines intersect this, as centres, with radius  $a e$ , describe the curves as in the copy.

EXAMPLE 43. To delineate the flutes in a pilaster, fig. 43. Let  $a b$  be the breadth; divide it into twenty-nine equal parts: each flute is three parts in breadth, and each fillet one. This gives to the pilaster seven flutes and




fig. 43.

eight fillets. Draw  $a c, b d$  at right angles to  $a b$ ; and parallel to these lines, from the first point next these, as at  $e$ ; at the fifth of these points, as at  $f$ ; the sixth, at  $g$ , draw lines. The first fillet is  $a e$ , the first flute,  $e f$ ;  $f g$  the second fillet,  $g h$  the second flute, and so on. The centres from which the termination to the flutes are described will be on the line  $s s$ , this being intersected by lines drawn parallel to  $a e$ , drawn through a point bisecting the fillet  $e f, g h, \&c$ .

EXAMPLE 44. To describe the curves in the twisted Doric column in fig. 44. Proceed as in

EXAMPLE 45, fig. 45. Draw the centre-line  $a b$ , and the line of base  $c e$ , the width  $d d$  being that below astragal in capital; join  $d c, d c$ . With distance  $c c$ , lay off on  $a b$  from  $a$  to  $e$ , and draw through this point the line  $g h$ , parallel to  $c a c$ . With half  $c c$ , as  $a c$ , lay off on  $a b$  to  $f$ . From  $f$  as centre, with  $f g$  as radius, describe the arc  $g c$ ; with  $f h$  as radius, from the

points *c* and *h* as centres, describe arcs cutting in *m*; from *m* as centre, with *m h* as radius, describe the arc *h c*. Make *e n* equal *g h*; with *e g*, or *e h*, lay



fig. 44.




fig 45.

off to *i*. From *i*, with *i p* as radius, describe the arc *p h*; from the points *g, o*, with same radius, describe arcs cutting in *s*; from *s*, with same radius, describe the arc *o g*. Next make *n t* equal to *o p*, and proceed as already described. The various centres are shown by the intersection of the arcs.

We now proceed to describe the method of laying out complete plans of houses. The first example of which we give in




fig. 46.

EXAMPLE 46, fig. 46, which is the 'ground-plan' of a pair of cottages, the division or party-wall being at  $mn$ ,  $AA$  the living-rooms,  $D$  the kitchen,  $E$  the scullery,  $F$  the back lobby,  $B$  the front lobby:  $aa$  are fire-places,  $b$  windows,  $d$  doors. The method of copying this is given in

EXAMPLE 47, fig. 47. Draw the line  $op$ , fig. 46, and bisect it, drawing from the point of bisection another line  $mn$  at right angles to  $op$ ; next, as in fig. 47, draw the lines  $cd$ ,  $ab$  at right angles, corresponding to  $po$ ,  $mn$  in




fig. 47.

fig. 46. Measure  $os$ , fig. 46, and lay it off from  $c$  to  $e$ , fig. 47; at right angles to this draw  $ef$ , and make it equal to  $sc$  in fig. 46. Draw  $cg$  at right angles to  $ce$ , and make it equal to  $ot$  in fig. 46; make the short 'return' at  $g$  equal to that at  $t$  in fig. 46. Parallel to  $gc$  draw  $gh$ , and make it equal to  $tu$  in fig. 46; make the return  $ho$  at right angles to  $gh$ , and equal to that at  $u$  in fig. 46. At right angles to this draw  $om$ , equal to  $uv$ :



make the return at  $m n$  equal to that at  $v$ , fig. 46; draw, parallel to  $a b$ , the line  $n o$ ; make  $o b$  equal to  $x d$ , fig. 46. The other half, which is exactly similar, should be drawn in simultaneously with the first. After the outline is thus obtained, the thickness of the walls should next be put in, as shown by the dotted lines in fig. 47. The example in fig. 47 is also designed to show the method of drawing a 'bedroom plan,' or floor above the ground one, from the data given by the lines on the latter. Suppose the upper figure (in 47) to be filled in with the partitions, fire-places, &c. &c., as in fig. 46, thus representing the ground-plan *finished*. By means of the T square produce all the boundary-lines of the upper figure to an indefinite distance on the paper below it, as shown by the lines 1, 2, 3, 4, 5; then proceed as before described in copying fig. 47 from the outline of fig. 46. The diagram will, it is hoped, be sufficiently explanatory of the method to be adopted, bearing in mind the lessons previously given. The pupil, in copying the various lessons given, should use a much larger scale than the limits of our pages will admit of. In the lower part of the figure 47, A is the principal bedroom, B the back bedroom, C the children's bedroom, D a small wardrobe, and E a small closet or bath room.

EXAMPLE 48. To draw the plan of cellar in fig. 48. Bisect  $a b$  in  $c$ , draw  $c d$ ; corresponding to these, on the board draw lines  $a b, c d$ . From  $c$  measure to  $a b$ . Draw from these, at right angles to  $a b$ , to  $e e$ ; parallel





fig. 48.

to  $a b$  draw  $e f$ , and parallel to  $c d, f g$ . Parallel to  $e f$  draw  $g h$ ; parallel to  $c d, h i$ . Join  $i i$ ; the outline of the plan is thus obtained. Put in the thickness of the walls, the horizontal lines 1 1 first, the vertical 2 2 thereafter; and the central partition  $m n$ , with fire-jambs  $o o$ . Put in also the windows  $s s$ , and stairs, as in the drawing.

EXAMPLE 49 is designed to show the method of getting the position of the doors and windows in the front elevation, from the data afforded by the plan A P P E, fig. 49. The plan below represents the ground-plan of a row of four cottages, of which one-half is the counterpart of the other; we have, therefore, only shown the one-half fully drawn. The line  $G F$ , dividing the length into equal parts, is prolonged to  $H$ ; the line  $a b r$  is drawn at right angles to this, and represents the ground-line: the distance of this above the plan will be decided according to circumstances, size of paper, &c. The openings of doors A, B, and E, are each bisected, and from the points lines are drawn parallel to  $G F$ , cutting the ground-line in the points  $u, v$ , and 3. In like manner, the windows C and D are bisected, and lines from the points drawn parallel to  $G F$ , cutting the ground-line in the points 1, 2.

The line 3 is the centre-line of end-door *p r*, the line 2 centre-line of window *n o*, line 1 centre-line of second window *h m*; the line *b*, of the window *d e*; *c*, of *f g*. The sizes of doors, &c., being previously ascertained, and



the scale known, the centre-lines obtained will enable the various parts to be drawn. In like manner, supposing the front elevation correctly drawn to scale given, also a rough sketch of ground-plan, with sizes, divide the length of front into two parts, and draw a line *G* at right angles to the ground-line. Draw any line parallel to the ground-line, at any distance below the elevation; this will form the back line of wall. Produce *G* to *F*; this will form the centre-line of the houses. Next bisect the breadth-line of doors in the points *a*, *u*, *v*, and *3*; and from these points, parallel to *G F*, draw lines to *A*, *B* and *E*; next divide the windows *h m*, *n o* in the points 1, 2, and draw as before lines to *c*, *d*. From the points thus given, if the pupil



has carefully attended to the foregoing lessons, he will have no difficulty in drawing the various parts accurately. In the plan here given B and E are the principal doors, I I the lobby, K the stairs to bedrooms, H the living-room, L the kitchen, M the scullery, P the back entrance.

In the work on Practical Geometry we have amply illustrated the method of reducing irregular figures by means of squares; to that work, therefore, as introductory to the present, we refer the reader for information; we here content ourselves with giving, in

EXAMPLE 50, fig. 50, an architectural subject, having a series of squares




fig. 50.




fig. 51.

drawn over its surface, preparatory to its being reduced one-half, as shown in EXAMPLE 51, fig. 51. Should it be required to enlarge fig. 50, all that is necessary is to draw the same number of squares, but of double the size, when, the various points being transferred to the proper places, an exact copy of fig. 50, but of twice the size, may be obtained.

In architectural drawing it is sometimes necessary to delineate the material of which the walls, &c., are constructed. Thus, in

EXAMPLE 52, fig. 52, a series of bricks built on one another is delineated. The bricks are so disposed as to 'break joint,' as it is termed;




fig. 52.




fig. 53.

that is, the solid part of *b* is placed over the joint formed by the juxtaposition of the bricks *a* and *c*. In ordinary work, bricks are used in two ways—as 'headers' and 'stretchers'—the 'headers' being placed across the wall, the 'stretchers' running along in the direction of its length. Thus, in

EXAMPLE 53, fig. 53, suppose *ab* to be the line of wall, the bricks *c c c* are 'stretchers,' and *d* a 'header.' The size of a brick of the ordinary dimensions is 9 inches long,  $4\frac{1}{2}$  inches wide, and 3 inches thick. Brick work is generally laid in two kinds of bond, termed 'English' and 'Flemish bond.' By the term 'bond' is meant the tie between the various members of a brick wall, and which is generally secured by the proper disposition of the bricks; this is effected by the arrangement of the 'headers' and 'stretchers.' Thus, in



EXAMPLE 54, fig. 54, which is a specimen of an elevation of a brick wall in 'English,' or as it is sometimes termed, 'old English bond,' where it con-




fig. 54.

sists of alternate layers of brick 'headers' and 'stretchers,' *aa* being the 'headers,' and *bb* the 'stretchers.'

EXAMPLE 55, fig. 55, shows a specimen of 'Flemish' bond, in which each row is made up of 'stretchers' and 'headers' laid alternately; *aa* are




fig. 55.

the former, *bb* the latter. In delineating plans, various methods are in use for filling up. Thus, in

EXAMPLE 56, fig. 56, *a* represents the method of filling up walls in a




fig. 56.

plan by means of cross lines *b* where the whole is dark, all openings, at

doors and windows, being left unshaded. The method of showing a chimney flue in the thickness of a wall is shown at *c*; another method in *d*. Stone work may be classed into three different kinds, as generally adopted; these are 'rubble,' 'coursed,' and 'ashlar.'

EXAMPLE 57, fig. 57, shows the method of delineating 'rubble work,' in which the wall is composed of stones of all sizes and shapes.



fig 57




fig. 58




fig. 59.

EXAMPLE 58, fig. 58, shows the method of delineating 'coursed work,' in which the stones are, to a certain extent, squared and set in courses: hence the term.

EXAMPLE 59, fig. 59, shows the method of delineating 'ashlar work,' in which all the stones are squared up to certain given sizes, and set in regular courses.

EXAMPLE 60, fig. 60, shows the method of delineating 'vermiculated' work, in which the surface of the blocks is left with rough projections, a




fig. 60.

narrow margin, tooled flat, being generally left round. This kind of work is used for 'keystones,' rusticated basements, doorways, &c.

The department now to be considered is that of

#### THE FIVE ORDERS—THEIR PROPORTIONS AND METHODS OF DELINEATION.

EXAMPLE 61, fig. 61, is an elevation of the 'Tuscan' order as generally received. The part from *a* to *c* is the 'pedestal,' from *b* to *c* the 'base,' from *c* to *d* the 'shaft,' from *d* to *e* the 'capital,' from *e* to *f* the 'entablature,'—the parts base, shaft, capital, and entablature, being termed a 'column.' The heights of the mouldings and the projections are all taken from the standard of measurement of each column; this standard being the diameter of shaft immediately above the base. This is divided into two equal parts, termed 'modules,' each of these again into thirty equal parts. The diameter is therefore divided into sixty equal parts; if necessary, each part is divided into sixty parts, called seconds. The standard is,



therefore, thirty parts equal one module; two modules equal one diameter, or sixty parts. According to Palladio and other authorities, the height of column (Tuscan) now under consideration is, including base and capital, equal to seven diameters. To obtain, therefore, the diameter of any column, its height being given, all that is necessary is to divide the height into seven equal parts, one of which is the diameter; or where, on the contrary, the diameter is given, seven times this will give the height of column, including base and capital. We may now proceed to describe the laying out of the various members of a complete 'order,' showing the proportions of the mouldings, their height and projections. Although some writers discard the pedestal as an integral portion or a correct feature of any of the orders, we follow the majority of those who adopt it as a distinguishing feature. It is not here our province to enter into a detail of the æsthetic rules guiding the laying out of the various orders; we merely give examples of the parts as generally received. To those of our readers anxious to go into the matter, we refer to more technical works, or the treatise in this Series entitled *Ornamental and Architectural Design*.

**EXAMPLE 62.** Suppose the line  $ab$  (fig. 62) to represent the diameter of a 'Tuscan' column. Dividing  $ab$  into two parts in the point  $c$ ,  $ac$ ,  $cb$  will be the two modules; dividing each module into three equal parts at  $d$ ,  $e$ ,  $f$ , and  $g$ , and these again into five equal parts, a scale will be constructed from which to measure the various mouldings. Number as in the drawing.




fig. 61.




fig. 62.

**EXAMPLE 63, fig. 63,** shows the method of proportioning the mouldings of the 'Tuscan pedestal.' Every pedestal is divided into three parts,—the 'base,' as  $AB$ ; 'die,'  $BC$ ; and the 'cornice,'  $CD$ . In the figure given the whole height of the pedestal is four modules, or  $ab$ , fig. 62. In order to keep our sketches within the limits of the page, we take the proportions from a scale, the divisions of which are only half the size of those in fig. 62. At  $a$ , fig. 63, draw a line, as  $iai$ , of indefinite length, and at right angles to it a line  $ab$ ; make  $ab$  equal to 2 diameters, or 4 modules,  $ac$  equal 26 parts,  $cd$  equal 4 parts,  $de$  equal 8. Make the 'die'  $en$  equal 2 modules 4 parts; make  $bf$  equal 3 parts,  $fg$  equal 8,  $gh$  equal 2,  $gn$  equal 4: the heights of



the 'members' will thus be found. The projections of the mouldings are all set out from the central line  $ab$ . From  $a$  with 53 parts lay off to  $i$ ,  $i$ , and from these draw lines meeting that drawn from  $c$ ; parallel to  $iai$  make




fig. 63.

$dm$  equal 51 parts, or set back the line  $md$  2 parts from the end of line  $c$ : make  $eo$  equal  $41\frac{1}{2}$ , and the die equal 40 parts; make  $bl$  equal 53 parts; make  $gs$  equal  $50\frac{1}{2}$ , and  $st$  equal 7, and  $nv$  equal  $eo$ .




fig. 64.

EXAMPLE 64, fig. 64, shows the 'base' of the Tuscan order. Draw the centre-line  $cd$ , put the 'plinth'  $ab$ , making  $cb$  equal 40 parts, and  $ce$  equal 15; make the 'torus' moulding in height equal  $12\frac{1}{2}$  parts. The centre  $m$  of the circular termination is found on the line  $f$ . Make the fillet  $h$  equal  $2\frac{1}{2}$  parts, and its projection from centre-line equal  $33\frac{3}{4}$ , or nearly 34 parts. To describe the 'apophygee,' by which the lines of shaft are connected with the base, see work on

Practical Geometry, where also the various forms of mouldings met with in the Orders may be found described, and the methods of delineating them.

EXAMPLE 65, fig. 65, is the Tuscan 'capital,' drawn to the same scale as the others. Draw  $cd$ ,  $ab$  at right angles; make  $ca$ ,  $cb$  equal  $22\frac{1}{2}$  parts, or  $ab$  equal 45; make the fillet of the astragal  $en$  equal  $24\frac{1}{2}$  parts, or  $nen$  equal 49 parts. Make  $gh$  equal 27;  $gi$ , the 'neck,' equal  $ab$  or 45 parts, and the fillet  $m$  above the neck equal  $en$ . Make the diameter of 'abacus'  $n'o$  equal 60 parts, or 1 diameter. These are the projections; the heights are as follows:—The fillet  $ef$  equal 2 parts;  $fg$  equal 4;  $gm$  equal  $8\frac{1}{2}$ ; the fillet above this  $1\frac{1}{2}$ ; the quarter-round  $mn'$  equal 10; the abacus or plinth  $n'o$  equal 10. The quarter-round begins at 1 division of the scale from  $s$ .




fig. 65.

EXAMPLE 66, fig. 66, is an elevation of the Tuscan 'entablature.' Every entablature consists of three parts,—the 'architrave'  $AB$ , the 'frieze'  $BC$ , the 'cornice'  $CD$ . Draw the line  $bd$  representing the centre line of column,




fig. 66.

and  $ab$  at right angles to it. The connection of the entablature with reference to the column will be seen in fig. 61. In the present figure the position is reversed. Make  $bc$ , the lowest 'fascia,' equal  $12\frac{1}{2}$  parts in height and  $22\frac{1}{2}$  in width from the central line  $bd$  to  $a$ . The upper 'fascia'  $ce$  is 17 parts in height and 24 in width; the 'fillet'  $ef$  is 5 parts in height and  $27\frac{1}{2}$  in projection; the height of the 'frieze'  $fg$  is 26 parts, and its projection  $22\frac{1}{2}$ ; the first moulding in the cornice  $gn$  (the cavetto), equal  $7\frac{1}{2}$  in height, and projection  $gh$  equal 24. Make the fillet equal  $1\frac{1}{2}$ , and its projection  $no$  equal 32; make the height of 'quarter-round' from  $n$  to  $p$  equal 9, and its

projection  $ps$  equal  $52\frac{1}{4}$ ; make  $pt$  equal 40, and join  $ot$ ; make the 'corona'  $pv$  equal 10 in height, and the 'fillet' above it equal 2; its projection equal  $54\frac{1}{4}$ . Put in the 'cyma recta'  $ic$   $x$ , equal 10 parts, the last fillet equal  $3\frac{1}{2}$ , and its projection equal 66.

EXAMPLE 67, fig. 67, shows the elevation of the 'Doric column,' with 'pedestal'  $ab$ ;  $bc$  the 'base,'  $cd$  the 'shaft,'  $df$  the 'capital,' and  $fe$  the




fig. 67.




fig. 68.

'entablature.' The height of the column, including base and capital, is equal to seven diameters.

EXAMPLE 68, fig. 68, is the elevation of half of the pedestal of the Doric column to same scale as the last example. Draw  $ap$   $ab$  at right angles, make  $ab$  equal to 4 modules 5 minutes, or 4 modules 20 minutes. Make the 'plinth'  $ac$  equal 26 parts in height; the 'fillet'  $cd$  equal  $1\frac{1}{2}$ ; the 'cyma recta'  $de$  equal  $6\frac{1}{2}$ ; the 'fillet'  $e$  equal 1; the 'cavetto'  $f$  equal 4. Proceed now to put in the cornice; make the top 'fillet' at  $b$  equal 2 parts; the 'corona' below equal  $6\frac{1}{2}$ ; the 'quarter-round' equal  $6\frac{1}{2}$ ; the 'fillet' equal 1, and the 'cavetto' equal 4. Put in the breadth of the 'die'



by measuring from  $f$  to  $n$ , equal 40 parts. From  $n$ , the face of the die, measure off to  $o$ , equal 16 parts; through  $o$  draw a line to  $p$  parallel to  $ab$ . From  $p'$  set off to  $s$ , equal 2 parts; from the line  $p'o$  to  $t$ , equal 11 parts. Make the projection of the cavetto at top of base and at cornice equal to 1 part from line of die. From  $v$  lay back to 4, equal 12 parts; from 2 to 3, equal  $5\frac{1}{2}$ . Put in the cyma at  $st$ , and the quarter-round from 4 to 3.

EXAMPLE 69, fig. 69, represents the base of the column now under consideration; it is sometimes termed the 'Attic base;' 10 parts are given to the 'plinth;' 7 to the 'torus;'  $1\frac{1}{2}$  to the 'fillet;' 4 to the 'scotia;' 1 to the




fig. 69.




fig. 70.

fillet above it;  $5\frac{1}{2}$  to the second torus, and 1 to the fillet above. The projections are set off from the centre-line  $ab$ , and are as follows, commencing with the 'plinth' equal 40; 'torus' equal 40; 'fillet' equal  $36\frac{2}{3}$ ; fillet beneath the second torus 35; second torus  $36\frac{2}{3}$ ; last fillet 34.

EXAMPLE 70, fig. 70, is the 'capital' of the Doric order. The various 'heights' and 'projections' are as follows, beginning with the fillet  $cd$ . The diameter of top of shaft is 52, or 26 parts on each side of the centre-line  $ab$ ; fillet  $cd$  is  $1\frac{1}{2}$  parts in height, and projection 28; the astragal or bead  $3\frac{1}{2}$ , projection 30; the neck 9 parts, projection 26. The three fillets below the quarter-round are together  $3\frac{1}{2}$  parts in height; this is divided into three equal parts, as in the drawing. The quarter-round is  $6\frac{1}{2}$  in height; the 'abacus'  $6\frac{3}{4}$ , and its projection 36: the quarter-round below it begins at a point 1 part back from end of abacus; the last fillet is 39.

EXAMPLE 71, fig. 71, shows an elevation of the Doric entablature. The line  $xx$  is the centre-line of column (see fig. 67), from which the projections are taken. The architrave  $af$  is composed of two fasciæ  $ab$ ,  $bd$ , with a fillet  $df$ . The 'guttæ' or 'drops' in the upper fascia  $bd$  are  $3\frac{2}{3}$  parts in height, surmounted with a fillet  $1\frac{1}{3}$ . The 'triglyph' is over this in centre of column, and its width is 30 parts; the distance between the 'triglyphs' is exactly a square, the side of which is the depth of the frieze  $fg$ ; the distances between the triglyphs are called 'metopes,' and are generally filled in with some ornament as in the drawing. The following are the heights of the various mouldings, with their projections:  $ab$  11 parts, projection from  $xx$  equal 26;  $bc$  equal  $9\frac{1}{2}$ ;  $cd$  equal  $3\frac{2}{3}$ ;  $de$   $1\frac{1}{3}$ , the projection of  $b$  and  $d$  equal 27; of the fillet  $fd$  equal 28, its height being 4 parts; the height of frieze  $fg$  equal 45;  $gh$  equal 5, projection of  $gh$  equal 27. Height of  $hk$

equal 5, the fillet 1; projection of  $h$  equal 32; of  $k$  35½; height of  $km$  equal 6; projection of  $m$  equal 64½; of  $vt$  equal 39½. Height of  $mn$  equal 8;




fig. 71.

$n$  o 3½; the fillet ¾, its projection 68. Height of  $os$  equal 6¾; fillet equal 2¼; projection 76. The method of drawing the 'triglyphs' and 'guttae' of this order is further elucidated by




fig. 72.

EXAMPLE 72. Let  $ab$  (fig. 72) be the height of 'frieze,' and  $cd$  semi-diameter of column at base. Make  $be$  equal 4 parts; the fillet  $ee'$  beneath this equal 2; and from  $e'$  to  $f$  equal 4. Divide  $cb$ ,  $bd$  each into six equal parts; and parallel to  $ab$ , draw through these lines as in the drawing to the line  $gh$ . On  $gc$ ,  $hd$ , lay off equal 2½ parts to  $m$ ,  $m'$ ; and with  $mn$  from  $m$ , lay off to  $o$ ; join  $no$ ,  $no'$ . On the lines 4 4 draw to  $ooo'$ , and put in the angular lines. Bisect the fillet  $be$  in the line  $ss$ ; from the points 1, 2, 3, &c. at  $f$ , draw lines to  $ss$  where this line intersects the vertical ones, dotted as in the sketch. These angular lines are only continued to the under side of fillet  $e'$ .

EXAMPLE 73 represents the elevation of the 'Ionic' order. A, fig. 73, is the base of pedestal, B the die, C the cornice, D the base of column, E the shaft, F the capital, G the architrave, H the frieze, I the cornice of entablature.




fig. 73.




fig. 74.

EXAMPLE 74, fig. 74, shows the elevation of half of Ionic pedestal; the line  $ab$  being that from which the projections are taken; the plinth  $bc$  is  $28\frac{1}{2}$  parts in height, and 57 in projection. The upper fillet  $ad$  is 2 parts high, and 57 in projection. The width of die is 42 parts. The whole height of pedestal from  $a$  to  $b$  is two diameters 34 parts, or 4 modules 4 parts. The heights of the other mouldings and projections are as follows,



commencing with the fillet at *e* above the plinth, which is in height  $1\frac{1}{2}$  parts, projection  $54\frac{1}{2}$ ; the cyma  $6\frac{1}{2}$  in height, projection  $48\frac{1}{2}$ ; the astragal  $2\frac{1}{2}$  in height, projection 50; the fillet 1, projection  $48\frac{1}{2}$ ; the cavetto,  $3\frac{1}{2}$ , projection 43. The height of die 87 parts; the height of cavetto above die 4 parts, projection 43; the fillet 1, projection 46; the astragal  $3\frac{1}{2}$ ; projection 48; the quarter-round 6; the corona 6, projection 55.

EXAMPLE 75, fig. 75, is the Ionic base, the line *ab* being the centre-line. The heights and projections are as follows: the plinth *cd* 10 in height, 42 projection; the torus, 8 height, 42 projection; fillet, 1 height, 37 projection; scotia, height 5; second fillet, height 1, projection  $34\frac{1}{2}$ ; second torus, height 5, projection 37; astragal, height 2, projection  $34\frac{1}{2}$ ; third fillet, height  $1\frac{1}{2}$ ; projection 33.




fig. 75.




fig. 76.

EXAMPLE 76, fig. 76, shows the elevation of Ionic capital drawn to same scale as the others. The plan of the capital is shown in

EXAMPLE 77, fig. 77, and the side view in




fig. 77.




fig. 78.

EXAMPLE 78, fig. 78. The method of describing the scroll termed the 'volute' is explained in

EXAMPLE 79, fig. 79. Draw *ab*, *cd* at right angles; let *ef* be the diameter of the eye of the volute corresponding to the breadth of the astragal *a* (see fig. 76); with half *ef* from the point where *ab*, *cd* intersect, describe a circle; within this inscribe a square. In fig. 80 the centre of the volute is drawn to a larger scale, to enable the pupil to mark out the centres used to describe the scroll in fig. 79. From *e*, fig. 80, with radius *ed*, describe the circle, and within it inscribe the square *abdc* corresponding to the square *egfh* in fig. 79. Through *e*, the centre, parallel to *ca* draw *fh*, and parallel to *ab*, *ig*; join the extremities, and form a square *ihgf*. Divide the diagonals *ig*, *fh* each into six equal parts, at the points 1, 2, 3, 4, 5, 6, 7, 8. At

these points draw lines at right angles, forming squares of which the corners are only given in the diagram to avoid confusion. Divide  $i k$  into four equal parts; from  $h$  lay one of these to  $m$ ; from  $i$  to  $n$ ; from  $f$  to  $o$ ; from  $g$  to  $p$ ; from  $8$  to  $s$ ; from  $1$  to  $t$ ; from  $5$  to  $v$ ; from  $4$  to  $x$ ; from  $7$  to  $y$ ; and so




fig. 79.

on to the point of the square corner at 3. These various points thus obtained are the centres from which the curve is described. Suppose the point  $i$ , fig. 79, to be the under line of abacus of capital, as  $b$  (see fig. 76), from the centre, on line  $eh$ , fig. 79, corresponding to the point  $c$ , fig. 80, with radius  $hi$  describe an arc of a circle to the point  $m$ , meeting the diameter of  $gh$  prolonged to  $a$ . From the point in the smallest square in fig. 79, corresponding to the point  $a$ , fig. 80, with radius  $em$ , fig. 79, describe an arc  $mn$ , meeting the diameter  $ef$  prolonged to  $c$ . From the point on the small square, fig. 79, corresponding to  $b$ , fig. 80, as a centre, with  $gn$  as radius, describe an arc  $no$ , meeting  $gh$  produced to  $b$ . From  $f$  as centre, with  $fo$  describe an arc to  $p$ , meeting line  $cd$ . From centre 1 (see fig. 80), with radius  $1p$  describe an arc to  $r$ . From centre 8 (see fig. 80), with  $8r$  as radius, draw an arc to  $s$ . From centre 4 (see fig. 80), with  $4s$  describe an arc to  $t$ ; from centre 5, with radius  $5t$ , describe an arc to  $w$ ; from centre 2 (see fig. 80), with radius  $2w$  describe an arc to  $g$ , and so on. To draw the interior curve proceed as follows: from the point  $n$  (see line  $if$ , fig. 80), with radius  $m1$ , describe an arc to the point 2 in the

line  $a b$ , fig. 79; from the point  $m$  (see line  $i h$ , fig. 80) with the radius  $m 2$ , an arc to the point 3 on the line  $c d$ , fig. 79; from the point  $p$  (line




fig. 80.

$h g$ , fig. 80), with the radius  $p 3$ , an arc to 4; from the point  $o$  (line  $g f$ , fig. 80), with radius  $o 4$ , an arc 5, and so on from the centres corresponding to the points  $s, t, v, x, y$ , &c., describing curves to the points 5, 6, 7, 8, 9, &c. fig. 79.

EXAMPLE 80, fig. 81, represents the 'Ionic entablature;'  $a b$  being the centre-line of column, and that from which the projections of the various members are taken. In succession, beginning from the point  $b$  upwards, the heights and projections of the various mouldings are as follows:—

1st height equal	$6\frac{1}{2}$ parts,	projection equal	$26\frac{1}{2}$
2nd "	" 2 "	" "	27
3rd "	" 8 "	" "	$27\frac{1}{2}$
4th "	" $2\frac{1}{2}$ "	" "	29
5th "	" 10 "	" "	$29\frac{1}{2}$
6th "	" 5 "	" "	33
7th "	" 3 "	" "	35
8th "	" 27 "	" "	33
9th "	" 5 "	" "	27
10th "	" 1 "	" "	32
11th "	" 6 "	" "	36
12th "	" 2 "	" "	37
13th "	" 7 "	proj. to $e$ equal 38, to $c$ equal 52	55
14th "	" 3 "	" "	60
15th "	" 4 "	" "	$63\frac{1}{2}$
16th "	" 4 "	" "	64
17th "	" 1 "	" "	64
18th "	" 7 "	" "	72
19th "	" 2 "	" "	

EXAMPLE 81, fig. 82, represents an outline sketch of the 'Corinthian column,' with pedestal complete. The height of column is  $9\frac{1}{2}$  diameters,



including base and capital. A is the base of pedestal, B the die, C the cornice, D the base of column, E the shaft, F the capital, G the architrave, H the frieze, I the cornice.

EXAMPLE 82, fig. 83, is the pedestal of the Corinthian order. The proportions are as follows, taking them in their order from  $b c$ : the plinth  $b c$ ,  $23\frac{1}{2}$  parts in height, its projection from the central line  $b d$  to  $a$  57 parts;




fig. 81.

the torus, height 4, projection 56; fillet  $\frac{3}{4}$ , projection 55; cyma 5, projection 47; fillet 1, projection 47; cyma  $3\frac{1}{2}$ , projection 42; die 3 modules  $4\frac{1}{2}$  parts; projection of die, 42 parts; the cavetto in cornice  $3\frac{3}{4}$ , projection 43; fillet  $\frac{3}{4}$ , projection 46; quarter-round  $4\frac{3}{4}$ , projection 50; corona  $4\frac{1}{2}$ , projection 53; cyma  $3\frac{1}{2}$ , projection 57; the top-fillet  $2\frac{1}{2}$ , projection 57.

EXAMPLE 83, fig. 84, represents the base of the order, of which  $ab$  is the centre line. The heights in the progression of their order, commencing with  $b c$ , are as follows: 10, 7, 2, 1, 4,  $\frac{1}{2}$ , 2, 6,  $2\frac{1}{2}$ , 2. The projections, beginning with  $b d$ , are as follows: 42, 42, 38, 37, 32, 37, 35, 32.

EXAMPLE 84, fig. 85, represents the capital of the order. The diameter of shaft at the neck is  $52\frac{1}{2}$  parts; the fillet  $1\frac{1}{2}$ , its projection 56; the astragal 4, projection 60. The height from  $a$  to  $b$  is 70 parts, the projection from  $b$  to  $c$  46, the projection from  $b$  to  $e$  60. Join  $ef$ , prolong  $af$ ,  $b e$  to  $g$  and  $h$ ; join  $gh$  by a line parallel to  $ba$ , and mark off on it from  $gh$ , as in the sketch. From the points obtained draw




fig. 82.

lines parallel to  $b e$ ; the intersection of these with  $e f$  will give the position of the acanthus leaves. The method of laying out the plan of this capital




fig. 83.




fig. 84.




fig. 85.

is shown in fig. 86, where  $ab$  is the diameter of shaft at neck,  $ce$  corresponding to the distance  $bc$ , fig. 85. The centre of the circle of which  $dd$  is a part, is found by the intersection of the lines at  $f$ .

EXAMPLE 85, fig. 87, shows a form of capital of this order, with the ornaments filled in.

EXAMPLE 86, fig. 88, is the 'Corinthian entablature.' The heights of the different mouldings, commencing with  $ab$ , are as follows:  $6, 1\frac{3}{4}, 8\frac{1}{4}, 1\frac{3}{4}, 10\frac{1}{2}, 5, 2\frac{1}{2}, 28\frac{1}{2}, 4\frac{1}{2}, 1, 5\frac{1}{2}, 1, 4\frac{1}{2}, 1, 7\frac{1}{2}, 2\frac{1}{2}, 1, 7\frac{1}{2}, \frac{2}{3}, 3, \frac{2}{3}, 6, 2\frac{1}{4}$ . The projections, beginning with  $ac$ , are as follows:  $26, 26\frac{1}{2}, 27, 27\frac{1}{2}, 28, 29\frac{1}{2}, 34\frac{1}{2}, 26, 26\frac{1}{2}, 32, 34, 35, 40, 58\frac{1}{2}, 60, 62, 62\frac{1}{2}, 66, 74$ .

EXAMPLE 87, fig. 89, represents the outline of the Composite order with pedestal complete: the letters and parts correspond




fig. 87.

with those given in fig. 82, where the pedestal is delineated. Its height, including base and capital, is 10 diameters.




fig. 86.




fig. 88.

D




fig. 89.



EXAMPLE 88, fig. 90. The pedestal. The heights, commencing with *b c*, are as follows: 33,  $4\frac{1}{2}$ , 1, 3,  $1\frac{1}{2}$ ; 1, height of die *d e* 4 modules 5 parts. The height of mouldings in cornice, beginning at *e*, are as follows:  $1\frac{1}{2}$ , 3,  $8\frac{1}{2}$ , 1,  $5\frac{1}{2}$ ,  $3\frac{1}{2}$ ,  $2\frac{1}{2}$ . The projections, beginning with *a b*, are 57, 57, 55, 46, 45, 42,  $44\frac{1}{2}$ , 47,  $52\frac{1}{2}$ , 53; top-fillet 57.




fig. 90.




fig. 91.




fig. 92.




fig. 93.

EXAMPLE 89, fig. 91, represents the base of the order. Heights, beginning with  $bc$ , 10, 7,  $\frac{1}{2}$ ,  $2\frac{1}{2}$ ,  $\frac{1}{2}$ , 2, 2,  $\frac{1}{2}$ , 2,  $\frac{1}{2}$ ,  $4\frac{1}{2}$ , 2, 1; projections, beginning with  $bd$ , 42, 42, 38, 36, 37, 37, 36, 36, 37, 36, 34.

EXAMPLE 90, fig. 92, represents the capital of the order. The semi-diameter of shaft at neck is 26 parts; the fillet  $\frac{1}{2}$  in height and 27 in projection; the astragal 4 in height and 29 in projection. The height from  $b$  to  $a$  is 70, projection from  $a$  to  $c$  45, and to  $d$  60; the heights on the line  $fc$  are used by the intersection of the line  $dc$  to find the height of the ornament. (See example 84.) Another form, with the ornaments filled up complete, is given in

EXAMPLE 91, fig. 93.

EXAMPLE 92, fig. 94, is the Composite entablature. The heights of the mouldings, beginning with  $bc$ , are as follows: 12,  $2\frac{1}{2}$ , 15,  $1\frac{1}{2}$ ,  $3\frac{1}{2}$ , 4, 2, 30,




fig. 94.

2, 2, 5,  $\frac{1}{2}$ ,  $3\frac{3}{4}$ ,  $1\frac{3}{4}$ ,  $6\frac{1}{2}$ ,  $1\frac{1}{4}$ ,  $2\frac{1}{2}$ ,  $9\frac{1}{2}$ ,  $3\frac{3}{4}$ , 1, 8,  $2\frac{1}{4}$ . The projections, beginning with  $ba$ , are 26, 28, 29, 34, 37, 36, 32, 52,  $53\frac{1}{2}$ , 54, 55, 66, 67, 70, 78.

The next example shows the manner of delineating intercolumniations. By this term is meant the distance between two columns, as  $a$  and  $b$ .

EXAMPLE 93, fig. 95, which is the intercolumniation of the Tuscan order. The distance between the columns is 6 diameters, the general distance, however, being 4 diameters. The pupil, at this stage of his proceedings, should make drawings to a large scale, as of that in fig. 62 of the intercolumniation of all the orders, to assist him in which we here give the various distances for each. The distance between the Doric columns is equal to three diameters; the distance in the Ionic is two diameters and

a quarter; the distance between the columns in the Corinthian is two diameters and a quarter; and that of the Composite one diameter and a




fig. 95.

quarter to one diameter and three quarters. For the various species of intercolumniation, with their distinguishing names, see the work in this Series on *Ornamental and Architectural Design*.

Where it is necessary to introduce doors, windows, &c., thus widening the space between the columns to a greater extent than true proportion requires, 'coupled columns' are introduced, the distance between them being such as to allow of the proper projection of their 'capitals.'

EXAMPLE 94, fig. 96, shows coupled columns in the Corinthian order, where the space between the two columns is a little over two diameters.

*Pilasters* bear a considerable resemblance in their elevation to columns. The height of members and their projections are the same as the columns of the same order; the plan, however, instead of being circular as in columns, is square, the external surface being flat.






fig. 96.




fig. 97.

EXAMPLE 95, fig. 97, shows 'coupled pilasters' in the Corinthian order.

*Caryatides* are sometimes used in place of columns and pilasters. These are representations of the human figure. When female, they are known by the name as above; when male, as 'Persians.'

EXAMPLE 96, fig. 98, is an exemplification of a caryatides. As a series of columns at proper distances form a colonnade, so columns with arches between them, are termed *arcades*. The Tuscan arcade is given in

EXAMPLE 97, fig. 99. The distance between the columns *a* and *b* is six diameters; *A* is termed a 'pier,' *B* the 'impost,' *C* the 'archivolt,' and *D* the 'keystone.' A semi-diameter of column is laid from *c* to *d*, which gives the line of pier *h d*. The distance from *p* to *t* is six diameters and three-quarters; a line through *t* parallel to *ab* gives the height of im-



fig. 98.

post; the capital of impost is obtained by dividing  $gh$  into seven or eight equal parts, and giving one of these from  $m$  to  $n$ ; the width of archivolt  $so$  is equal to one-ninth part of  $gh$ ; the width of keystone at  $ef$  is equal to  $os$ . By drawing lines to  $e$  and  $f$  from  $t$ , the centre of the circle,  $mefs$ , the diverging lines will be obtained. To assist the pupil in making out





fig. 99.


examples of arcades in the other orders, we quote the following directions of a celebrated author on architecture as to proportions:—"The height of arches to the underside of their crowns should not exceed twice their clear width, nor should it be much less; the piers ought not to be less than one-third the breadth of the arch, nor more than two-thirds." The pupil desirous of studying the principles of architectural design may consult the work on *Ornamental and Architectural Design*, above noticed.

EXAMPLE 98, fig. 100, is an elevation of the Tuscan impost, with the heights and projections. The projections are set forward from  $b$  to  $k$ , in the line  $b c$ , the line  $b c$  representing the face of pier corresponding to the

line  $h d$  in fig. 99. The scale from which the measurements are taken is that in fig. 62. The figures 1, 2, and 3 denote the width of the mouldings on the archivolt  $c c$  (see fig. 99), and are set back on the line  $a k$  from  $b$ .



EXAMPLE 99, fig. 101, is the Doric impost. The heights are measured from the point  $b$  on the line  $b c$  representing the line of pier, as in last ex-



ample, the projections being set forward from  $b$  to  $w$  and  $t$ , the width of mouldings of archivolt, 1, 2, 3, 4, 5, being from  $b$  towards  $a$ .



EXAMPLE 100, fig. 102, is the Ionic impost, the projections, heights, and widths 1, 2, &c. of archivolt mouldings being set out as in last figure.




fig. 102.




fig. 103.

EXAMPLE 101, fig. 103, is the Corinthian impost. The projections




fig. 104.

being set out from the line  $c d$  towards  $e$ , the width of archivolt mouldings 1, 2, 3, &c., as  $a c$ , from  $c$  towards  $a$ .

EXAMPLE 102, fig. 104, is the Composite impost, the projections being set from the line  $b b$ . The scale from which the measurements should be taken is the same for all the imposts, being that in fig. 62.

EXAMPLE 103, fig. 105, shows a 'pediment.'  $c c$ , the tympanum, is generally filled in with sculpture. In our work on Practical Geometry, in




fig. 105.




fig. 106.




fig. 107.

the latter part, we have shown how geometry is made applicable to the construction of the various forms of arches, vases, and balustrades. We now give, in

EXAMPLE 104, fig. 106, an elevation of the Tuscan balustrade; and in EXAMPLE 105, fig. 107, an elevation of the Ionic.

The reader desirous of becoming acquainted with the members of the Grecian orders of architecture, and of the principles which regulate the proportions of various architectural features, of which the limits and nature of the present work do not allow us to give even a passing notice, is referred to the work previously mentioned, treating of architectural and ornamental design.

We now purpose giving examples of various architectural forms and decorations, useful to impart to the pupil a correct general idea of the method of proportioning doors, windows, &c.; and also serving as copies by which he may test his proficiency, and enable him to acquire that facility so requisite for the architectural draughtsman to possess. We shall first give forms of windows and doors.

EXAMPLE 106, fig. 108, is the elevation of an ordinary sash-window, the method of laying out of which was explained in Example 4.




fig. 108.




fig. 109.

EXAMPLE 107, fig. 109, is the elevation of a rustic window, with lozenge-shaped panes of glass. For the method of laying this out, see Example 5, fig. 5.

EXAMPLE 108, fig. 110, is an elevation of a three-light (Venetian) window, in the Italian style, drawn to a scale of one-fourth inch to the foot.

EXAMPLE 109, fig. 111, is a one-light window in the same style, to a scale of one-eighth inch to a foot.

EXAMPLE 110, fig. 112, is an elevation of a second-floor or bedroom




fig. 110.




fig. 111.



window in same style, with iron ornamental balustrade in front. As a general rule, the proportion of windows should be, height twice the breadth




fig. 112.




fig. 113.

for those on the ground-floor; those on the second floor the same breadth, but of less height.

EXAMPLE 111, fig. 113, is an example of a circular-headed window, with rusticated dressings.

EXAMPLE 112, fig. 114, is the front elevation of a projecting window, of which the side elevation is given to a scale of one-quarter inch to a foot, in

EXAMPLE 113, fig. 115, which is of the same scale as the above.




fig. 114.




fig. 115.

We shall now give examples of windows placed over windows.

EXAMPLE 114, fig. 116, is the front elevation of a bay-window in the light Italian style, the plan of which shows the three sides of an octagon,

with the bedroom-window over it ; the scale is one-fourth of an inch to the foot. The side elevation of the bay-window is shown in




fig. 116.

EXAMPLE 115, fig. 117, which is drawn to the same scale as above.

EXAMPLE 116, fig. 118, is the elevation of a bay-window on the ground-floor, in the Domestic Gothic style, with bedroom-window over it. The scale is one-eighth of an inch to the foot.

EXAMPLE 117, fig. 119, is another sketch, showing elevation of bay-window in Italian style, with bedroom-window over ; same scale as above.

EXAMPLE 118, fig. 120, shows the elevation of window over window in the Tudor style ; scale three-sixteenths of an inch to the foot.




fig. 117.




fig. 118.





fig. 119.




fig. 120.



EXAMPLE 119, fig. 121, is the front elevation of a bay-window on ground-floor, with projecting oriel window over it on bedroom-floor, in the Elizabethan or Jacobin style, drawn to a scale of one eighth inch to a foot. The side elevation of this drawing is shown in

EXAMPLE 120, fig. 122, same scale as above.

EXAMPLE 121, fig. 123, is a sketch, showing front elevation of Venetian or three-light window on ground-floor in Italian style, with bedroom-window over, with ornamental dressings and segmental pediment.




fig. 121.




fig. 122.




fig. 123.

We now proceed to give examples of doors, and windows over doors. First, as to doors, of which, in

EXAMPLE 122, fig. 124, we give the elevation of one in the Roman style.

EXAMPLE 123, fig. 125, is the front elevation of another form in the Italian style.




fig. 124.




fig. 125.






fig. 126.

EXAMPLE 124, fig. 126, is the elevation of a form suitable for a public building, with vermiculated dressings. Another form is given in

EXAMPLE 125, fig. 127.

EXAMPLE 126, fig. 128, is front elevation of door, with vermiculated dressings, in the Italian style (of which fig. 111 is the window belonging to same design), with circular-headed window over it. The scale is one-quarter inch to the foot.

EXAMPLE 127, fig. 129, is front elevation of door, to the house of which fig. 114 is the principal window. The scale is one-quarter inch.



fig. 127.





fig. 128.




fig. 129.

EXAMPLE 128, fig. 130, is front elevation of door at the end of house, with window on second floor over it. This example is in the same style as fig. 123, which is the principal window to same house of which this figure is the door. The scale is one-eighth inch.

EXAMPLE 129, fig. 131, is front elevation of doorway to house of which fig. 116 is the window, having over it a circular-headed window in bed-



room-floor. The scale is one-quarter inch. The side elevation of the door in this drawing is given in

EXAMPLE 130, fig. 132, the scale of which is the same as above.

EXAMPLE 131, fig. 133, is front elevation of principal door to a house, with bedroom-window over it, with ornamented dressings. Scale one-eighth inch.

*The central portion of house (of which figs. 123 and 130 are parts of the same design).*




fig. 131.




fig. 130.




fig. 132.

EXAMPLE 132, fig. 134, is front elevation of principal door to house, in Domestic Gothic style (of which the drawing in fig. 118 is the window), with closet-window over it on bedroom-floor.




fig. 133.




fig 134.




fig. 135.

EXAMPLE 133, fig. 135, is elevation of principal entrance to house, in Tudor style, of which the drawing in fig. 120 is the window.

EXAMPLE 134, fig. 136, is elevation of principal entrance, with window over it, of house of which fig. 121 is the window.

We now give the elevations of a few examples of fireplaces, the first of which is in the Tudor style, and is shown in

EXAMPLE 135, fig. 137. The part *c* shows the profile of the mouldings. Another form, in same style, is given in

EXAMPLE 136, fig. 138.

EXAMPLE 137, fig. 139, is in the Italian style; A shows the profile of




fig. 136



the skirting-board running round the room, of which the lines at B show the front elevation.

EXAMPLE 138, fig. 140, is in the Elizabethan style. In these examples




fig. 137.




fig. 138.

of fireplaces, we have only shown half, the other being an exact counterpart. The pupil should, however, draw them complete, the line *ab* being the centre-line.




fig. 139.





fig. 140.

We now proceed to the more elaborate copies, in which the pupil will find ample exercise for the display of that facility for copying which the foregoing lessons have been designed to impart. From the limits of the page we have been compelled to adopt a small scale; it is to be understood, however, that the pupil is to copy them to a larger one, at least twice as large as those we have adopted.

EXAMPLE 139, fig. 141, is the front elevation of a school-house, with railings to the front. Another design is given in

EXAMPLE 140, fig. 142.



EXAMPLE 141, fig. 143, is the front elevation of a row of cottages, drawn to a scale of one-eighth inch to the foot.




fig. 143.



EXAMPLE 142, fig. 144, is the front elevation of a shop-front, drawn to a scale of one-eighth inch to the foot.





fig 144.

EXAMPLE 143, fig. 145, is front elevation of a greenhouse, of which the end elevation is given in

EXAMPLE 144, fig. 146, and the plan in

EXAMPLE 145, fig. 147 ; they are all drawn to a scale of one-sixteenth inch to the foot.



In order to give the pupil an idea as to the way in which a set of plans are set out for the guidance of the artisan and workman, we have prepared a series of drawings illustrative of the design for a town-house in the Italian style. It is necessary to mention that the design when finished is double that given in the drawings; two houses being attached, the other half of the drawing (not shown) is the exact counterpart of that given in the copy. The scale we have adopted is one-eighth inch to the foot. The pupil, in copying them, should make the scale at least double this, or one-fourth inch to the foot.




fig. 146.





fig. 147



EXAMPLE 146, fig. 148, is the “*basement plan*” of the house; the line  $ab$  is the centre-line.



EXAMPLE 147, fig. 149, is the "ground plan."




fig. 149.

EXAMPLE 148, fig. 150, is half plan of *first bedroom floor*.




fig. 151.

fig. 150.



EXAMPLE 149, fig. 151, is the half plan of *second bedroom floor*.

EXAMPLE 150, fig. 152, is half *front elevation*. From the minuteness of the scale we give detail drawings, which will show the decorative portions more fully than in the sketch. The first of these we give is the elevation




fig. 152.

of the first bedroom-floor window, and its section drawn to a larger scale; it is shown in

EXAMPLE 151, fig. 153. The front elevation of cornice is given in EXAMPLE 152, fig. 154; and the section showing form of bracket in





fig. 154.

EXAMPLE 153, fig. 155. The elevation of chimney is shown in  
 EXAMPLE 154, fig. 156, and the elevation of cornice and finial to prin-  
 cipal entrance is given in  
 EXAMPLE 155, fig. 157.




fig. 155.




fig. 156.




fig. 157.



EXAMPLE 156, fig. 158, is *end elevation*. We give this in full, as one side is different from the other. The *half back elevation* is given in





fig. 158.

EXAMPLE 157, fig. 159. The *transverse section* is taken across the *plan*. The right-hand half of this is given in



EXAMPLE 158, fig. 160; the left-hand half in  
EXAMPLE 159, fig. 161. The same letters of reference apply to both  
drawings. The pupil should make this section in one complete drawing.

We have only shown one part  
up to the roof-line, the other  
without the chimney-shaft,  
but showing the roof-timbers.  
The pupil should be able to  
finish these sections from the  
other drawings.




fig. 160.




fig. 161.



EXAMPLE 160, fig. 162, is half plan of roof, showing timbers. The other half, showing the slated surface, and position of flues, is given in




fig. 162.



through both, and secured by a screw bolt, and nut. The arches *m, m* are described from their centres *g, g* on the lines *h, h*, springing from the pillars *c, d*: the arch *n* is described from centre *i*.




fig. 164.

EXAMPLE 163, fig. 165, is a transverse section of a fireproof cottage.




fig. 165.



In our work in the present series, the *Illustrated Drawing-Book*, we have given directions for delineating architectural subjects perspective. We now present a few additional examples, which will serve as copies with which the pupil may still further exercise himself in architectural drawing; premising that in this department he is supposed to have the advantage of a knowledge of the rules by which objects are put in perspective, and a facility in copying such subjects as depend chiefly on the eye, aided by a readiness of hand in pencilling. These desiderata are indispensable before the pupil can copy the examples which we are now to present to his notice; for assistance as to the readiest means of attaining them, we beg to refer the pupil to the above work.

EXAMPLE 164, fig. 166, is the perspective drawing of a public asylum, in the Italian style, with a campanile tower.




fig. 166.




fig. 167.



fig. 168.



EXAMPLE 165, fig. 167, is a perspective sketch of the interior of an apartment, with carved panels, &c., in the Italian style.

We now present a few examples of churches perspectively delineated; the first of these,

EXAMPLE 166, fig. 168, is a perspective drawing of a church in the Early-English style.



fig. 169.

EXAMPLE 167, fig. 169, which is in the Early-Decorated or Pure Geometrical style. The peculiarities of the various styles of Gothic architecture will be seen by an inspection of figs. 202, 203, &c.

EXAMPLE 168, fig. 170, is in the Transitional from Decorated to Perpendicular.

EXAMPLE 169, fig. 171, is in the Middle or Second Pointed Period.






fig. 170.



fig. 171.

EXAMPLE 170, fig. 172, is in the Early-Decorated style.



fig. 172



EXAMPLE 171, fig. 173, is in the Early-English style.



fig. 173.



EXAMPLE 172, fig. 174, represents in perspective the interior of part of a church (the nave) in the Norman style. This is considered to be a fine specimen of the architecture of the period.



fig 174.

EXAMPLE 173, fig. 175, represents the interior of the Lady chapel in Tynemouth Priory church; the architectural features of which belong somewhat both to the Decorated and Perpendicular styles.



fig. 175.

We now proceed to give a few illustrations of architectural ornament; the drawings of which are nearly in all the instances produced by hand,



only here and there aided by the drawing-board and instruments. A knowledge of pencil-sketching is therefore necessary for these examples.




fig. 177.




fig. 176.




fig. 178.



fig. 179.




fig 180.

EXAMPLE 174, fig. 176, is the elevation and end view of a pierced parapet in the Elizabethan style.

EXAMPLE 175, fig. 177, is a side elevation of panelling, in the same style as the last figure.

EXAMPLE 176, fig. 178, is another example of a pierced parapet, in the same style as in fig 177.

EXAMPLE 177, fig. 179, is the front elevation of a key-stone.

EXAMPLE 178, fig. 180, is another example of raised panel, in the same style as fig. 177.






fig. 181.



fig. 182



fig. 183.



fig. 184.

EXAMPLE 179, fig. 181, is a design for a Gothic panel.

EXAMPLE 180, fig. 182, is the Grecian ornament known as the "honeysuckle."

EXAMPLE 181, fig. 183, is part of an ornamented frieze for the Ionic column.

EXAMPLE 182, fig. 184, is an ornament sometimes used in filling up the space called "metopes" in the Doric order. (See p. 42, ex. 71.)

EXAMPLE 183, fig. 185, is a design for a frieze and cornice.




fig. 185.

EXAMPLE 184, fig. 186, is the elevation of a sculptured pilaster forming part of a chimney-jamb.



EXAMPLE 185, fig. 187, is a form of ornament sometimes used in place of balustrades.

EXAMPLE 186, fig. 188, is an example of bracket, of which the side view is given in

EXAMPLE 187, fig. 189.




fig. 186.




fig. 187.

EXAMPLE 188, fig. 190, is a perspective view of a Grecian 'scroll truss.'

EXAMPLE 189, fig. 191, is an elevation of an Elizabethan scroll truss.

EXAMPLE 190, fig. 192, is an exemplification of the ornament called the 'fret.' Another form is given in

EXAMPLE 191, fig. 193.

EXAMPLE 192, fig. 194, is an exemplification of the ornament termed the 'guilloche.' Another example is given in

EXAMPLE 193, fig. 195.






fig. 188.




fig. 195.



fig. 191.




fig. 189.




fig. 190.




fig. 192.




fig. 193.




fig 194.

In the work on *Practical Geometry* we have given examples of outlines of vases, with the methods of describing their curves. We now present a specimen with the outlines ornamented.

EXAMPLE 194, fig. 196.

EXAMPLE 195, fig. 197, is an example of 'vase and pedestal.'




fig. 196.

G 2




fig 197



EXAMPLE 196, fig. 198. Another example of vase, with the outlines ornamented.

EXAMPLE 197, fig. 199. Design for a Gothic monument.



fig. 198.



fig. 199.



EXAMPLE 198, fig. 200. A design for a fountain.

EXAMPLE 199, fig. 201, is the elevation of a stained window in the geometrical style.




fig. 201.




fig. 200.

We now, as concluding this department of our treatise, proceed to give a series of designs, exemplifying by inspection the peculiarities of the various periods of Gothic architecture as generally received.

EXAMPLE 200, fig. 202, is an elevation of a Norman window.




fig. 202.

EXAMPLE 201, fig. 203, is the Early-English (or Lancet). This style




fig. 203.



succeeded the Norman, and was followed by the Decorated, the tracery of which was distinguished by geometrical lines, as in

EXAMPLE 202, fig. 204; and in the later instances by flowing lines, termed curvilinear, as in



fig. 204.

EXAMPLE 203, fig. 205. The Perpendicular is derived from the Deco,




fig 205.



rated ; its distinguishing feature is the perpendicular lines of the tracery, as seen in

EXAMPLE 204, fig. 206.

For further information on the styles and peculiarities of Gothic Architecture, see the work on "Ornamental and Architectural Design."





fig. 206.

# ENGINEERING DRAWING.

EXAMPLE 1, fig. 1. Bisect any two of the piers, as  $ab$ ,  $cd$ , in the points  $a$  and  $c$ . Draw lines  $am$ ,  $cd$ ; put in the piers; divide  $ac$  into two equal



portions at the point  $h$ ; parallel to  $cd$  draw  $hi$ ; measure to  $i$ . This will be the centre of the arch. In like manner the aqueduct arches in

EXAMPLE 2, fig. 2, may be drawn; the lines  $d, c, a, b$  being the lines of the piers;  $g$  the centre of the under, and  $h$  that of the upper arches. The various parts of an arch are shown in




fig. 2.

EXAMPLE 3, fig. 3, where  $ab$  is the 'span' of the arch;  $ed$  its 'rise';




fig. 4.

$a d b$  the inside curve, called the 'soffit,' or 'intrados;' the key-stone is  $g$ .



The exterior or upper curve of the arch is called the 'extrados.




fig. 3.




fig. 5.

EXAMPLE 4, fig. 4, is an elevation of bridge with semi-elliptical arch. For method of describing this form see *Practical Geometry*.

EXAMPLE 5, fig. 5, is elevation of the timber framing or 'centering' of a bridge.

The method of delineating the various features of a country or district in a map is shown in




fig. 6.

EXAMPLE 6, fig. 6, where A represents a piece of inland water or lake ;  
E E a river, proceeding from this ; B the garden attached to the mansion ;

c a hill, with trees on its summit; C C, near the river E E, represents rising ground on its margin; H H plantations of trees; O O a swamp or morass; K K meadow-lands; L L a public highway. In the following illustrations the features are shown on a larger scale, as in

EXAMPLE 7, fig. 7, which represents a hilly or mountainous ridge.




fig. 7.

EXAMPLE 8, fig. 8. Rising ground near a river.

EXAMPLE 9, fig. 9. The same.



fig 8.



fig. 9.

EXAMPLE 10, fig. 10, represents a river, with small stream issuing from it and traversing a meadow. In copying this, the pupil should fill up the whole of the part representing the extent of meadow (within the boundary-line) as in the corner of the illustration now given.

EXAMPLE 11, fig. 11, represents swampy ground with trees.



fig. 10.



fig. 11.



EXAMPLE 12, fig. 12, represents a river entering the sea; the coast is delineated as in the sketch.




fig. 12.

EXAMPLE 13, fig. 13, represents part of a sea-line of coast *cc*, with sandy shoal *bb*, and swampy morass *aa*.




fig. 13



fig. 14.

EXAMPLE 14, fig. 14, represents the method of delineating a rock, used in marine maps. A range of rocks is represented in EXAMPLE 15, fig. 15, and a rock surrounded by sand in EXAMPLE 16, fig. 16.



fig. 15




fig. 16.



fig. 17.

EXAMPLE 17, fig. 17, represents a sandy shoal. The method of delineating water in a basin or harbour is shown in



EXAMPLE 18, fig. 18. The manner of representing blocks of houses in a town or suburban district map is represented in




fig. 19.

EXAMPLE 19, fig. 19. This example is also designed to show the use of squares in reducing or enlarging maps. The principle of this method has been fully described in *Practical Geometry*.




fig. 18.




fig. 20.

EXAMPLE 20, fig. 20, is the same subject as in the previous figure. The pupil, aided by the letters of reference and the figures, should have no difficulty in finding the various points in fig. 20 from fig. 19, and *vice versa*, if

the plan is fig. 20 to be enlarged twice, as in fig. 19. Irregular portions of maps may be copied by adopting offset lines, as in .

EXAMPLE 21, fig. 21, which represents part of a river, which is required to be copied and enlarged as below. Draw any line  $cd$ ; from any scale set off distances, as  $cg = 50$ ,  $gh = 60$ , and so on. Next draw a line, as  $po$ , corresponding to  $cd$ ; from  $p$  set off distances corresponding to those in  $cd$ , but taken from a scale larger than that of  $cd$ . From the same scale as that from which the measurements on  $cd$  were taken, measure the lines drawn at the various points at right angles to  $cd$  to where they touch the outline of the lowest side of river, as  $g = 40$ . Make the line  $t$  the same distance, but taken from its proper scale; by proceeding thus, points will be found, by tracing through which, an outline will be obtained equal to that of the copy. The angle  $dcb$  is equal to  $40^\circ$ . The pupil should extend this principle of copying irregular figures, by which he will be enabled to judge of its utility in practice.




fig. 21.



fig. 22.



fig. 23.

## REFERENCES.

GREEN.....

RED.....

fig. 24.


We now give a few examples of the lettering attached to maps and plans.

P A R I S H O F

fig. 25.



EXAMPLE 22, fig. 26, shows the compass-mark in plans, by which the directions are obtained. The *fleur-de-lis* always points to the north.



EXAMPLE 23, fig. 27, represents the plan of part of a district through which a road *ab* is to be cut. The section of this is in




fig. 27.

EXAMPLE 24, fig. 28. The parts filled in with small dots represent hollows filled up; the cross-lines point where a cutting is made. The horizontal line *cd* is termed the 'datum line.' See article 'Levelling' in the work on *Practical Mathematics* in this series.




fig. 28.



fig. 29.

EXAMPLE 25, fig. 29, represents a section of road, showing method of delineating it.



EXAMPLE 26, fig. 30, represents the rocks at the side of a section of a railway cutting.



fig. 30.




fig. 31.

EXAMPLE 27, fig. 31, represents the method of delineating an embankment faced with rubble masonry.

EXAMPLE 28, fig. 32, represents a breakwater formed of large stones thrown together, sloping outwards to resist the action of the waves.

EXAMPLE 29, fig. 33, is the section of a stone pier, where *aa* is the face toward harbour; *bb* that to the sea; the interior is filled with round stones, as *cc*. The plan of a retaining wall is shown in



fig. 32.




fig. 33.

EXAMPLE 30, fig. 34, where *bcc* is the stone facing; *d* the stones used for filling up.




fig. 34.

EXAMPLE 31, fig. 35, represents the footings *B* of a pier of a bridge resting on a sand foundation at *A*.




fig. 35.




fig. 36.

EXAMPLE 32, fig. 36, represents piles of wood driven into the ground, supporting masonry. A section of a coffer-dam in a bed of 'beton' is shown in




fig. 37.

EXAMPLE 33, fig. 37, where *cc* is the mass of masonry, resting on the mass of beton; *dd* represents mud; *ee* the main piles and 'wales,' and *ff* the cross-pieces; *b* represents the clay-pudding between the piles, which serves to keep out the water from the interior. For explanation

of the various terms here used, see treatise on *Mechanical and Civil Engineering*.

EXAMPLE 34, fig. 38, is elevation of factory-chimney, of which the transverse vertical section is given in




fig. 38.




fig. 39.

EXAMPLE 35, fig. 39. The scale for both figures is given with fig. 38.



## SECTION III.

### MECHANICAL DRAWING.

IN this department we purpose explaining, by the help of appropriate diagrams, the easiest methods of delineating various portions of machinery. In this, as in the others just treated of, a knowledge of the constructions which we have given in *Practical Geometry* will be essential. The preliminary lessons also of the department of this work on Architectural Drawing will be of use in enabling the pupil readily to master the lessons we now place before him.

EXAMPLE 1, fig. 1. represents a 'bolt,'  $cb$ , with the solid head  $e'd$ , and movable 'nut,'  $g'g$ . This is used for strongly fastening various portions of machinery together. For examples of the method of using this, see our work on *Mechanics and Mechanism* in this Series. To draw the figure now given :—Suppose the copy to be without the centre-line ; bisect  $e'e'$  in the point  $a$ , draw  $ab'$ . On the paper on the drawing-board draw two lines  $e'e'$ ,  $ab'$  at right angles to each other ; with  $ae'$  from the copy measure from the point of intersection of the above lines on the board  $a$  to  $e'e'$  ; from  $a$  measure to  $b$  ; from  $b$  with distance  $ae'$  measure to  $dd$  ; join  $de'$ ,  $d'e'$ . From  $a$  measure to  $c$  and  $b'$  ; from these points with  $ae'$  measure to  $g'g$ ,  $g'g$  ; join  $g'g'$ ,  $gg$ . From  $b$  measure to  $hh$  ; parallel to  $ab'$  from  $h$ ,  $h$  draw lines meeting  $g'g$ .




fig. 1.

EXAMPLE 2, fig. 2. Bisect the line  $bb'$  of the copy in the point  $a'$ , and draw  $a'b$ . On the paper on the board draw two lines corresponding to these, intersecting at the point  $a'$ .\* From  $a'$  measure to  $b$ ,  $b'$ , from  $a'$  measure to  $c$  ; with  $a'b$  from this point measure to  $ff$  ; draw a line parallel to  $b'b$  through  $e$  ; join  $f'b$ ,  $f'b'$ . From  $a$  or  $c$  measure to  $d$ , and through this draw a line parallel to  $b'b$ . From  $c$  measure to  $g$ ,  $g$  ; join  $g'g'$  by perpen-

\* To avoid repetition, the pupil is requested to observe that, in all the lessons, the centre-lines drawn on the various diagrams must be drawn on the paper on the board, it being understood that where a copy is presented him in this book, or elsewhere, without centre-lines being given on it, that these should be adopted and drawn in faint lines, so that data may be obtained from which to take measurements. By dint of practice the facility for copying without these will be attained, or, at least, they will be sparingly required. As the pupil proceeds, he will the more readily decide as to the quickest method of finding datum points from which to take measurements.

dicular lines to  $gg$  on the line  $ff$ . From  $d'$  measure to  $e$ ; draw a line through this parallel to  $a'b'$ ; from  $e$  measure to  $e'e$ ; from  $d$  measure to  $h'h$  on the line  $g'g$ ; join  $h'e$ ,  $h'e'$ . Where we use the terms 'measure from'—as measure from  $a'$  to  $b'$ —we mean, in all instances, that the measurement  $a'b'$  is to be taken from the copy and transferred to the paper on the board, from the point thereon corresponding to the point  $a'$  in the copy. Again, when we say 'measure from  $d'$  to  $b'$ ', we wish the pupil to take the measurement  $a'b'$  from the copy, transferring it to the line on the paper




fig. 2.

corresponding to the line  $b'a'$  in the copy, from the point on the paper corresponding to the point  $a'$  in the copy. Hence the pupil will observe the use of datum-lines—as  $a'b$ ,  $b'a'b'$ —from which to take the measurements from the copy; these to be transferred to the paper on the board on which the fac-simile is to be constructed. As a means of enabling the pupil readily to decide on datum-points from which to take measurements, we explain another method of copying the last figure. Draw any line  $b'a'b'$ , assume any point on it, and draw there a line at right angles to  $b'a'b'$ . The intersection of these lines will represent the point  $b'$  in the diagram just given. From  $b'$  measure to  $f$  in the copy, and transfer it from  $b'$  to the line which is at right angles to  $b'a'b'$  as to  $f'$ ; from  $f'$  draw a line parallel to  $b'a'b'$ . From  $b'$  measure to  $b'$ , or from  $f'$  to  $f'$ ; join  $b'f'$ . The part  $b'f'$ ,  $f'b'$  will thus be put in: the part up to  $g'd'g'$  may thus be put in without the use of a centre-line. The part to  $e$  can be quickest put in by using one; however, it may be done as follows:—Measure from  $d$  to  $h$ ; from  $h$  draw a line to  $m$ , at right angles to  $g'd'g'$ ; with  $de$  or  $ae'$  measure to  $e$ , and draw through this a line  $e'e$  parallel to  $a'b'$ . From  $m$  measure to  $e$ , and from  $e'$  to  $e$ ; join  $h'e$ ,  $h'e'$ . In the following diagram the use of the circle is shown.

EXAMPLE 3, fig. 3. Draw any two lines on the board corresponding to  $ae$ ,  $g'g'g'$  in the copy. From  $g$  measure to  $b$ ,  $c$ , and  $d$ ; from  $g$  measure to




fig. 3.




fig. 4.

$g'g'$ , and from  $b$  to  $b'b'$ ; join  $g'g'$  to  $b'b'$  by lines at right angles to  $g'g'$ . From  $c$  measure to  $c'e$ ; join  $b'e$ ,  $b'e'$ . From  $d$ , with  $da$  as radius, describe a semicircle  $da'a'$ ; by lines parallel to  $cb$  join  $a'a'$  with the line  $c'e$ .

EXAMPLE 4, fig. 4. Draw on the board two lines corresponding to  $ab$ ,  $hh$  in the copy. From the point of intersection  $c$  measure to  $a$ ,  $b$ , and  $h'h$ ; through  $a$   $b$  parallel to  $h'h$  draw lines  $h'h'$ ,  $h'i$ ; through  $h$   $h$  parallel to  $a$   $b$



draw lines meeting those in the points  $h' h'$ ,  $h' i$ . From  $c$  with  $cg$  put in the circle; from  $c$  measure to  $e$ ,  $e$ . From these points, with  $e' e'$  as radius, describe the circles, and also the interior ones, as  $ef$ .

EXAMPLE 5, fig. 5. Draw on the board, lines  $ab$ ,  $cc$  at right angles, intersecting at  $e$ , corresponding to those in the copy. From  $e$  measure to  $a$




fig. 5.




fig. 6.

and  $b$ ; from these points draw lines parallel to  $ce$ , from  $ab$  measure to  $b' b'$ ,  $e' e'$ . From  $e$  measure to  $cc$ ; join  $ce'$ ,  $cb'$ ,  $ce'$ ,  $cb'$ . The radius of the circle in the centre is  $eg$ .

EXAMPLE 6, fig. 6. Draw lines corresponding to  $bdc$ ,  $hh$  in the copy. From  $g$  measure to  $d$ ; put in from  $d$  as a centre, the circles  $d' d'$  and  $e' e'$ . From  $g$  measure to  $h$ ,  $h$ , and parallel to  $bd$  from these draw lines touching the circle,  $d' d'$ . From  $g$  measure to  $g'$  and  $f'$ ; from these points measure to  $o' o'$ ; through  $o' o'$  draw lines parallel to  $hh$  and to  $bd$ .

EXAMPLE 7, fig. 7, represents a set of what are termed 'speed pulleys' (see *Mechanics and Mechanism*). Draw any two lines corresponding to  $a b$ ,




fig. 7.

$g' g$ . From  $c$  measure to  $d$ , through this draw a line parallel to  $g' g$ ; measure from  $c$  and  $d$  to  $g'$ ,  $g$ . Bisect the distance  $dc$  in  $d'$ ; from  $d'$  as a centre, with  $d' g'$  as radius, describe the arcs joining the lines through  $g' g$ ,  $g' g$ . In like manner, measure from  $c$  to  $e$  and  $f$ : the points  $f'$ ,  $e'$  will be the centres of the arcs joining the lines drawn through  $e$  and  $f$ .



EXAMPLE 8, fig. 8, represents a projecting 'snug,' by which two parts may be joined by means of a bolt secured by a nut, passed through holes bored in each. Draw the line




fig. 8.

to it. From  $a$  measure to  $b$ , and put in the various horizontal lines and the base; from  $b$  measure to  $c$ , and parallel to  $ab$  draw a line from this point. From  $c$  measure to  $d$ ; from  $d$  as centre with radius  $dc$  describe the curve. From  $f$  measure to  $e$ ; a line drawn from this, parallel to  $ab$ , gives the end-line. The centre  $g$  (as also  $d$ ) is found by trial on the copy, and the points transferred to corresponding parts on the board. The line  $dc$  represents one method of transferring them.

EXAMPLE 9, fig. 9, represents a side view of a 'pulley,' or 'drum,' showing the arms and centre. Draw any two lines corresponding to  $ab$ ,




fig. 9.




fig. 10.

$cd$ . From  $g$  as centre, with  $gb$  as radius, describe the circle, and also the interior circle  $g'g'$ ; from  $g$  with  $gh$  put in the small circle representing the diameter of the centre or eye of the wheel. From the lines 1, 1 with distance 1, 2 lay off on either side of all the centre-lines of the arms; next, from the points where the interior circle cuts these lines at the points  $g', g'$ , lay off on each side equal to half the thickness of the end of the arm as it joins the inside of wheel. Join the points thus obtained with those previously obtained on the centre of the wheel, as 2, 2.

EXAMPLE 10, fig. 10, represents the plan of a circular cylinder or receptacle, the small circles showing the position of the circular heads of the bolts used for attaching the cover to the main body of the receptacle. The method of finding the centres of the small circles is as follows: Draw any two lines  $ae, bd$ ; from the point of intersection as centre, with radius  $ab, ac$ , describe circles; bisect the distance between these, as  $bc$ , in the point  $f$ . From  $a$  as centre, with  $af$  as radius, describe a circle  $fed$ : the centres of the small circles will be found on this line. Find the position

of any two of the circles, as  $fe$  or  $ed$ ; transfer these points to the board. In the copy, the centres of four of the circles will be found where the diameters  $ea$ ,  $bd$  cut the circle drawn through  $fd$ . Count the number of circles between  $f$  and  $e$ , or  $e$  and  $d$ ; divide the circular line passing through  $f$ , and between  $e$  and  $f$  or  $e$  and  $d$ , into as many equal parts as will give as many centres as there are circles in the copy: these points will be the centres of the circles.

EXAMPLE 11, fig. 11, represents the plan of a small thumb-wheel attached to the head of a screw-bolt, by which it may be easily moved by means of the finger and thumb. From  $a$  with  $ab$  describe a circle, draw the diameter  $db$ ; divide the semicircle  $db$  into four equal parts in the points  $ef$ ; from  $a$  draw lines through  $ef$ ; and continue these to cut the other semicircle. From  $a$  measure to  $n$ , the centre of the circles forming the ends. With  $an$  describe a circle: the points on the radial lines, as  $n$ ,




fig. 11.




fig. 12.




fig. 13.

where this intersects them, are the centres of the circles which terminate each radial arm. From  $a$  describe the small circle  $ac$ ; from the points where this intersects the radial lines, as  $c$ , lay off on each side of these the distance  $co$ ; join the points thus obtained on the circle  $aco$  with the extremities of the circular ends. Another way of joining the radial arms to the centre or eye may be understood by inspection of the diagram in fig. 12, where  $a$   $b$  are the centres of the circles, part of which joins the arm with the centre.

EXAMPLE 12, fig. 13. Draw any two lines corresponding to  $ag$ ,  $dd'$  in the copy; from the point of intersection  $c$  measure to the points  $h$ ,  $g$ ; through these draw lines parallel to  $dd'$ . From  $h$ ,  $g$  measure to  $m$ ,  $m$ ,  $h$ ,  $h$ ; join  $m$ ,  $h$ ; put in, in like manner, the internal parallelogram  $l$   $i$   $l$   $i$ . From the point  $c$ , with radius  $ce'$ ,  $ca'$ , and  $ca$ , describe the circles as in the copy, meeting the line  $m$ ,  $m$ .



EXAMPLE 13, fig. 14, represents plan of part of a 'valve-plate.' From any centre  $a$  describe a circle  $ab$ , and one within this, as  $ac$ ; continue this last all round, the part from  $m$  to  $p$  being afterwards rubbed out when




fig. 14.

the drawing is finished and inked in. From  $a$  with  $ad$  put in part of a circle  $ede$ . From  $d$  measure to  $e$ ,  $e$ , and through these draw lines to the points, as  $g$ , on each side of the line  $f$ . On each side of the line  $ah$  measure to  $p$  and  $m$ , also from  $n$  to  $o$ ; join  $mo$ . Put in the circles at  $n$  and  $h$ ; join them as in the drawing.

EXAMPLE 14, fig. 15, represents the plan of a 'lever.' Describe the circle  $a$ , draw through  $a$  the diameter  $bad$ ; from  $a$  measure to  $c$ ; put in the circle  $cd$ . Bisect  $ac$  in  $e$ , and through this draw a line at right angles to  $ad$ , as  $ff$ . In the copy take the points  $f$  (where  $ef$  intersects the curve),  $h$  and  $g$  (where the curve  $hg$  touches or joins to the circles described from  $c$  and  $d$ ). By means of these points (see the problem in the work on *Practical Geometry*, to find the centre of a curve, three points in that curve being given), the centre  $m$  will be found.

EXAMPLE 15, fig. 16, represents the method generally employed of constructing the central part of a "spur-wheel." The circles  $c$ ,  $f$ , and  $m$  are




fig. 15.




fig. 16.

described from the centre  $d$ ; the circle  $m$  is divided into as many equal parts as there are arms in the wheel, any central point of these, as  $m$ , being adopted as the datum-point from which to take the measurements. The space between any two of these arms, as  $ab$ , is bisected, and a line,



as  $df$ , drawn. By measuring from  $f$  to  $e$ ,  $g$ , the centres of the curves at  $e$  and  $g$  will be obtained; the centre of the curve  $ab$  is also on the line  $df$ .

EXAMPLE 16, fig. 17, represents the plan of a pulley with curved arms. The method of describing these is explained in




fig. 17.




fig. 18.

EXAMPLE 17, fig. 18. The first operation necessary to be done is to find in the copy fig. 17, the centres of the circles forming the curves: these must be found by trial. Next draw two lines at right angles, as in fig. 18, intersecting in the point  $a$  corresponding with the centre  $c$ , fig. 17. From  $a$  describe circles representing the rim and the eye of the wheel in last figure. From  $c$ , in fig. 17, measure to the centre  $b$ , from which the curve  $d$  is described, and from  $a$ , fig. 18, a circle  $ao$ : on this line the other centres, as  $e$ , fig. 17, will be found. In like manner, from the centre  $c$ , fig. 17, measure to  $a$ , from which the curve  $as$  is described, and from  $a$ , fig. 18, describe the circle  $gh$ . On this will be found the second set of centres. From  $d$  measure to  $h$ , from  $h$  to  $n$ , from  $n$  to  $f$ , and from  $f$  to  $g$ : these are the various centres. Or the curves next the eye may be drawn in first, and the curves with radius  $as$  be described, to meet these from the circle  $gh$ . In this example the arms are of uniform breadth; where they get gradually less from the centre or eye of the pulley outwards, the method of describing them may be learned from

EXAMPLE 18, fig. 19. The points from which the curves are drawn must be found, and corresponding points transferred to the paper, as in last example. Two circles, as  $d, o$ , will thus be obtained, in which the centres of the various curves will be found. Put in the circle representing the eye of the pulley, and draw a diameter  $ab$ ; draw a line in the copy corresponding to this, and measure from  $b$  to the point representing the centre of the circle from which the curve  $cc$  is drawn, as  $d$ ; transfer this to the copy, and from  $d$  with  $dc$  draw the curve  $cc$ ; from  $c$  measure to  $f$ , thus giving the breadth of arm at eye; from  $f$ , with the radius of the curve  $f$  taken from the copy, cut the circle  $o$  in  $o$ ; from this point with same radius describe the curve  $fg$ . The various points denoting the centres of the curves are given in the circles, the points  $ee$  being those where the curves join the central circle or eye of the pulley.




fig. 19.

EXAMPLE 19, fig. 20, represents the bottom part of foot of a cast-iron framing. Draw a line  $cd$ ; from  $c$  measure to  $a$  and  $b$ ; through these




fig. 20.




fig. 21.

draw lines perpendicular to  $cd$ ; with  $ac$  from  $a$  describe the curve  $co$ . From  $b$  measure to  $e$ . Find the centre of the curve joining  $oe$ , at  $f$ . Find by any of the methods already described the point  $m$ ; join  $md$  by the curve.

EXAMPLE 20, fig. 21, represents part of the frame-work forming the support for the bearings  $c$  in which vertical spindles revolve. Draw  $ab$ ,  $ad$ ; measure from  $a$  to  $d$  and  $c$ ; draw  $ce$  at right angles to  $ad$ . From  $c$  measure to  $f$ , and from  $f$  draw to  $g$  parallel to  $ab$ ; from  $a$  measure to  $h$  and  $m$ . The centre of the curve joining  $fm$  will be found at  $g$  on the line  $fg$ . The method of filling-in the drawing is shown by the other half.




fig. 22.

EXAMPLE 21, fig. 22, represents the outline of side elevation of framing. Draw the line  $ab$ , and at right angles to it  $2'd$ ; measure from  $2'$  to  $a'a'$ , and to  $3'$ . Through these points draw lines  $dd$ ,  $a'c'$ ,  $a'c'$ ; join the points  $c', d$  by the part of the circle, as in the diagram. From  $2'$  measure to  $f$ , and draw the line  $tft$ ; from  $f$  measure to  $t, t$ ; from these points draw lines parallel to  $2'd$ . From  $t$  measure to  $n$ ; draw  $nn'$ , and from  $n, n'$ , with radius  $nn'$ , describe curves meeting, as in the drawing. From  $f$  measure to  $f$ , and draw  $hfh$ ; from  $h, h$  with radius  $hh$  describe curves meeting in  $g$  on the line  $vv$ . The curves 5, 6 and 3 are described from the centres  $n', n$ , and 4, 6 from centre  $h$  on the left hand side of  $ff$ . The lines  $mm, oo$  are joined by curves described from the centre 3, which centre is found by describing arcs from the points  $m, o$  with any radius greater than half  $mo$ , and joining the intersection of these arcs by a line as in the copy.




fig. 23.

EXAMPLE 22, fig. 23, is another outline representing the side elevation of framing. The curve  $h$  is described from the centre  $f$  on the centre-line  $bf$ ; the centre-lines of the other parts are at  $m, e, d$ , and  $c$ .




fig. 24.

EXAMPLE 23, fig. 24, is another form of framing. The centre of the curve  $n$ , joining the lines from  $m, m$ , is at  $h$ , on the centre-line  $oh$ ; the centres  $d, d$  are on the line drawn through  $c$  to  $h$ , parallel to  $mm$ ; the centre of the circle  $e$  is at  $g$ .



EXAMPLE 24, fig. 25, represents the front elevation of a 'cross head' and 'side levers.' The centre-lines are  $a d$ ,  $e h$ ,  $v v$ . The plan is shown




fig. 25.

below, the lines of which are obtained by continuing those of the upper figure, as in the drawing.




fig. 26.

EXAMPLE 25, fig. 26, represents the front elevation of the cover for a gas retort. The centre of the parts  $b$ ,  $c$ , and  $d$  is at  $a$  on the line  $d e$ ; the centre of the curve joining  $o p$  at  $m$ , on the line  $n m$ .

EXAMPLE 26, fig. 27, represents the 'transverse vertical section' of a boiler  $a b$ , and its brick 'setting.' From  $a$  with  $a b$  describe the circle  $a b$ ; from  $a$  measure to  $c$ : draw  $c d$ , and from  $d$ ,  $d e$ . From  $d$  measure to  $g$ , from which point a line drawn parallel to  $c d$  marks the point  $f$ , where the curve  $f o$  terminates at the boiler. The point  $n'$  is the centre of the curve  $f o'$ ; transfer this part from  $f$  to  $n'$ , and describe  $o' f$ . From  $a$  measure to the lines  $o s$ ,  $n m$ , and draw lines through these parallel to

$c d$ ; measure from  $d$  to  $r$  and  $g$ . The centre of the curve  $o' h$  is at  $s$ , and that of the curve  $h r$  at  $m$ .

EXAMPLE 27, fig. 28, represents an 'angular-threaded screw.' To copy it, proceed as follows: Measure from  $a$  to  $d$ , and from  $d$  to  $e$ , 1, 2, 3, &c.

These are the points through which the centre-lines of each thread are drawn. From  $a$  measure to  $f$ , and draw  $fg$ ; and from  $a$  to  $b$  and  $c$ , and




fig 27




fig. 28.

draw  $bn$ . From  $f$  on the line  $bf$  measure to  $g$ , and from  $b$  to  $n$ ; through  $d$  draw  $ndg$ , and parallel to this, through  $e$ , 1, 2, 3, &c., draw lines. Next, from  $d$  measure on each side of  $dg$ , equal to half the breadth of each thread, to  $n'$ . These lines terminate at the perpendicular  $bn$  join the angles as in the drawing.

EXAMPLE 28, fig. 29, represents a 'square-threaded screw.' From  $e$  measure to  $a$ ;  $ab$ ,  $bc$ ,  $cd$ , represent the thickness of each thread and the




fig. 29.




fig. 30.

distance between them; the line from  $g$  is the line of the inside of the screw, the line  $f$  the outside line of the threads. The last example shows the method of copying this.

EXAMPLE 29, fig. 30, represents a 'helix' of wire,  $ad$  being centre-line,  $de$  being half the thickness of the coil, the lines from  $c$ ,  $b$  intersecting

those drawn parallel to  $d$ , giving the centre of the circles forming the termination of coils.

EXAMPLE 30, fig. 31, represents another form of screw.




fig. 31.



fig. 32.




fig. 33.

EXAMPLE 31, fig. 32, represents the Archimedean, or endless screw ; and another form is given in

EXAMPLE 32, fig. 33, where  $ab$  is the central shaft round which the helix or thread  $ee$  is coiled, according to a determined pitch.

EXAMPLE 33, fig. 34, shows the method of drawing-in the teeth of wheels. Let  $cx$  be the diameter of wheel from centre to outside of teeth.




fig. 34.

The circle, of which part is shown, and of which  $cb$  is the radius, is termed the 'pitch-circle or line.' It is on this line that the number of teeth are marked off. Having ascertained the diameter of pitch-line, the depth of teeth, and the number of them, divide the pitch-circle into as many equal parts as there are to be teeth in the wheel, and proceed as follows : Let  $a, b, 4, 5$ , &c., be the divisions on the pitch-circle representing the centres



of teeth; divide the distances between them into two equal parts, as at  $d$ . From  $d$  as a centre, with  $db$  on both sides of the point  $d$ , describe arcs of circles as  $fb$ , joining the pitch-circle and the outer circle, giving the termination of the teeth as the circle  $x$  1. Proceed in this way till all the arcs are made to join the circle  $x$  1, 2  $d$ . The bottom of the teeth are formed by radial lines drawn as from  $ce$  to the centre  $c$ , as in the diagram. The forms of teeth are various (see treatise on Mechanics in this series). For the method of describing different curves, and of setting out teeth of wheels and pinions, see treatise on Mechanical and Civil Engineering. The method of drawing the side elevations of toothed wheels may be seen in

EXAMPLE 34, fig. 35. The small dotted circles show another method of describing the form of teeth. The manner of delineating bevil-wheels




fig. 35.

(for the nature and operation of these see treatise on Mechanics in this series, at pp. 51, 52), may be gathered from the two following figures.

EXAMPLE 35, fig. 36. Let  $ab$  represent the centre-line of the wheel,  $cd$  the line of its greatest diameter or 'pitch-line,'  $f$  the line giving termination of teeth,  $dm$  being the breadth of the teeth. The teeth on the part between  $cr$ ,  $dm$  converge to the point  $b$ ; those between  $kd$ ,  $cn$  to the point  $a$ , on the line  $ahg$ ,  $efb$ . It is foreign to the purpose of this work to go into the subject of the teeth of wheels, belonging, as it does, to a strictly technical department; we cordially recommend, however, to the pupil anxious to study this interesting and important department, Buchanan's work on *Mills and Mill Gearing*, edited by Sir John Rennie, and published by Weale of Holborn; and the *Engineers' and Machinists' Assistant*, by Blackie of London and Glasgow. Both of these works, although somewhat high-priced, abound in valuable information. We may possibly, at some future time, publish a companion to this treatise, which may serve as a guide or introduction to the sciences of Civil and Mechanical Engineering. To proceed, however, with our explanation. The method of copying the teeth of bevil-wheels may be seen in

EXAMPLE 36, fig. 37, where  $ab$  is the centre-line of wheel,  $cg$  the pitch-line,  $eh$  the line terminating the teeth on the back part of the wheel  $eg$ .





Mechanical drawings are reduced or enlarged quickest by means of what are termed 'proportional compasses.' If these are not available, 'scales' should be drawn from the different figures. Thus, to reduce the drawing in




fig. 38.

EXAMPLE 37, fig. 38, of which the scale is given in fig. 39. Suppose the drawing is to be reduced one-half, a scale half fig. 39 is to be made, as in fig. 40; and as each measurement is taken in the compasses from fig. 38, it must be applied to the scale in fig. 39. Suppose this distance is found to be 6 feet, then the distance of 6 feet must be taken from the scale of fig. 40; and the line thus obtained must be drawn in a situation corresponding to that in fig. 38. The result will be a reduced copy, one-half of the size, as shown in




fig. 39.




fig. 40

EXAMPLE 38, fig. 41. To reduce by means of the proportional compasses: Having previously set them at the desired mark on the scale attached to each instrument, according to any proportion as desired, all that is necessary to be done is to take any measurement with one end; the distance corresponding to this, reduced or enlarged, is given in the other ends. This being transferred to paper, the desired distance is obtained at



once. To reduce by means of the ordinary compasses, without the use of a scale as just described in figs. 38-41, is a matter requiring greater time, and accuracy of adjustment of the compasses is indispensable. Suppose  $a b$ , fig. 41, to be the points representing the intersection of the centre-lines




fig. 41.




fig. 42.




fig. 43.

of the parts A, B with the base-line  $a b$ , and that a line corresponding to the centre-line from  $a$  was drawn on paper, and that half the distance  $a b$  in the copy was to be transferred to the paper, half of  $a b$  would have to be found in the first place on the copy and transferred. By proceeding thus, a copy of fig. 41, but only half its size, would be obtained. The enlargement of figures is exactly the *converse* of what we have described in figs. 38-41.

EXAMPLE 39, fig. 42, is a drawing which is reduced half in

EXAMPLE 40, fig. 43.




fig. 44.




fig. 45.




fig. 46.

Mechanical drawings are delineated in three ways: as 'plan,' shown in EXAMPLE 41, fig. 44, which represents the 'plan' of a pulley or solid drum. In 'elevation,' as in

EXAMPLE 42, fig. 45, which is the elevation of fig. 44. Elevations may be 'front,' 'back,' 'end,' or 'side.' In 'section,' as in

EXAMPLE 43, fig. 46, which is a transverse vertical section of figs. 44 and 45. The same letters of reference denote the same parts in these three sketches. Sections may be divided into 'transverse' and 'longitudinal,' these being either vertical or horizontal.

In finished outline-drawings, shadow-lines are made use of. The light, in the generality of examples, is supposed to come from the top and left-hand side of the drawing, thus throwing the right hand and under lines

in shadow. These are therefore made darker in inking-in the drawing, as exemplified in

EXAMPLE 44, fig. 47, which is the outline drawing of 'front elevation of high-pressure steam-engine,' the plan of sole-plate of which is given in




fig. 47.

EXAMPLE 45, fig. 48.




fig. 48.

We now proceed, as a conclusion to this department, to give a few examples to serve as copies to the student, in copying which he will find his operations much facilitated if he has paid full attention to the preliminary lessons. The copies given in perspective are set out by the rule given in the section on 'Perspective' in the *Illustrated Drawing-Book*, to which we refer the reader.




fig. 49.



EXAMPLE 46, fig. 49, is a transverse vertical section of Nasmyth's steam ventilating-fan.

EXAMPLE 47, fig. 50, is a longitudinal vertical section of an aerated water-machine.




fig. 50.

EXAMPLE 48, fig. 51, is a longitudinal and transverse vertical section of a smoke-burning furnace.




fig 51.

EXAMPLE 49, fig. 52, is 'side elevation' and 'end elevation' of Roberts' Alpha clock.




fig. 52

EXAMPLE 50, fig. 53, represents a side-elevation of a corn-mill, with section (vertical) through the grinding-plates.

EXAMPLE 51, fig. 54, is a perspective view of another form of portable corn-mill.





fig. 53.




fig. 54.



EXAMPLE 52, fig. 55, is a transverse vertical section of the 'patent conical flour-mill,' of which the perspective view is given in




fig. 55.

EXAMPLE 53, fig. 56.




fig. 56.

EXAMPLE 54, fig. 57, is front elevation of a fixed high-pressure steam-engine.




fig. 57.



EXAMPLE 55, fig. 58. is a perspective sketch of a fire-engine.




fig. 58.

EXAMPLE 56, fig. 59, is a side elevation of a 'disc-pump.'




fig. 59.



EXAMPLE 57, fig. 60, is a perspective sketch of a 'drug-grinding-machine.'




fig. 60.



EXAMPLE 58, fig. 61, is the side elevation of an 'American wood-burning locomotive.'




fig. 61.

In the various examples we have given, the pupil will perceive the method in which the various parts are shaded in order to represent round parts, flat, and so on. Mechanical outline-drawings may be shaded by means of lines, as in the examples we have given, thus imitating the manner in which engravers give the desired shade. When this is carefully executed in fine ink lines, regularly drawn, the drawing has a fine effect when finished, accurately presenting the appearance of roundness in some portions, and flatness in others, according as the subject requires. When this method is considered too tedious, the shades may be put in with Indian ink and a camel-hair brush, the appearance of roundness being imparted by first putting in a part of uniform depth in tint, and washing the outside line of this with a brush moistened in pure water, until the colour gradually blends into the tint of the surrounding paper. The depth of tint towards the outside part should be gradually got up to the desired point by repeated operations, the colour used being of a light shade. The addition of a little blue imparts a softness to the Indian ink, which is agreeable to the eye. Cast-iron surfaces are represented by a bluish-gray tint, malleable iron by a light blue; brass surfaces by a faint yellow, brick by a reddish yellow, faintly mottled with a shade darker of the same colour; stones by a faint yellow, with horizontal streaks of a darker tint; wood by yellow, with vertical streaks of a faint black; water by faint blue, with horizontal streaks or lines of a faint black: these look best when put in carefully with the pen and square, as in the diagram in fig. 62. These are the principal shades of colours required in mechanical drawings. The colours generally required are Indian ink, gamboge, Prussian blue, Indian red, lake, and sepia.

The reader desirous of extending the range of his copies will find numerous excellent examples of machinery in the work on Mechanics in this series.



fig. 62.

THE END.



WARD, LOCK, & CO.'S  
 CATALOGUE  
 OF  
**JUVENILE BOOKS**  
 AND  
 Illustrated Volumes  
 FOR  
**REWARDS AND PRESENTS.**

---



ENTIRELY NEW EDITIONS.

*ANDERSEN'S FAIRY TALES.*

**FAIRY TALES.** By HANS CHRISTIAN ANDERSEN. With 100 Illustrations and Fourteen Coloured Pictures, and Life of the Author. In One handsome Volume, demy 8vo, cloth gilt, 7s. 6d.

**HANS ANDERSEN'S STORY BOOKS FOR THE YOUNG.** With Coloured Plates and other Illustrations. Fcap: 8vo, cloth gilt, 1s. each:—

1. THE CHRISTMAS TREE.
2. THE GARDEN OF PARADISE.
3. THE WILLOW TREE.
4. THE SILENT BOOK.
5. THE LITTLE MERMAID.
6. THE SILVER SHILLING.

7. THE SNOW QUEEN.
8. THE ICE MAIDEN.
9. LITTLE IDA'S FLOWERS.
10. LITTLE TUK.
11. WHAT THE MOON SAW.

London: Ward, Lock, & Co., Warwick House, Dorset Buildings, Salisbury Square, E.C.



**ANDERSEN'S POPULAR TALES FOR CHILDREN.** With many full-page and other Illustrations. Crown 8vo, cloth gilt, 3s. 6d.; with Coloured Illustrations, cloth gilt, gilt edges, 5s.

**ANDERSEN'S STORIES FOR THE YOUNG.** With many full-page and other Illustrations. Crown 8vo, cloth gilt, 3s. 6d.; with Coloured Illustrations, cloth gilt, gilt edges, s.

### BEETON'S "GOOD-AIM" SERIES.

CLOTH GILT, ONE SHILLING EACH.

Cloth extra, bevelled boards, gilt edges, 1s. 6d.

*The feature of this series of Books is to encourage in childhood a spirit of love, gentleness, and cheerfulness, while affording amusement and interest.*

1. **THE ORIGINAL POEMS FOR CHILDREN.** By ANN and JANE TAYLOR.
2. **THE BASKET OF FLOWERS;** or, Piety and Truth Triumphant.
3. **ELLEN'S IDOL.** By the Author of "Tiny."
5. **SERMONS ON THE WALL.** By JOHN TILLOTSON.
6. **GOLDY AND GOLDY'S FRIENDS.** By MARY DENSEL.
7. **THE ONE THING NEEDFUL;** or, Ethel's Pearls.
8. **I DON'T KNOW HOW.** By E. STUART PHELPS, Author of "The Gates Ajar."
9. **SAYINGS AND DOINGS OF CHILDREN.** By the Rev. J. B. SMITH.
10. **TINY.** By ELIZABETH STUART PHELPS.
11. **TINY'S SUNDAY NIGHT.** By E. STUART PHELPS.
12. **THE ORPHAN BOY;** or, From Peasant to Prince.
13. **TOM, TOM, THE PRINTER'S SON.** A Boy's Story, Related by Himself.
14. **ONLY A DANDELION.** By the Author of "Stepping Heavenward."
15. **FOLLOW ME.** By the Author of "Stepping Heavenward."
16. **NEW YEAR'S BARGAIN.** By SUSAN COOLIDGE.
17. **IN THE BEGINNING;** or, From Eden to Canaan.
18. **CONQUERORS AND CAPTIVES;** or, From David to Daniel.
19. **THE STAR OF PROMISE;** or, From Bethlehem to Calvary.
20. **THE HISTORY OF THE ROBINS.** By Mrs. TRIMMER.
21. **HYMNS FOR INFANT MINDS.** By ANN and JANE TAYLOR.
22. **RHYMES FOR THE NURSERY.** By ANN and JANE TAYLOR.
23. **LITTLE SUSY'S SIX BIRTHDAYS.** By the Author of "Stepping Heavenward."
24. **LITTLE SUSY'S LITTLE SERVANTS.** By the Author of "Stepping Heavenward."
25. **LITTLE SUSY'S SIX TEACHERS.** By the Author of "Stepping Heavenward."

**PICTURE A B C.** (WARD, LOCK, AND CO.'S.) With numerous Illustrations. Fcap. 8vo, cloth, 6d.

**EASY STEPS FOR LITTLE LEARNERS.** With Pretty Pictures. Crown 8vo, cloth, 1s.

**CHILD'S FIRST BOOK OF NATURAL HISTORY.** Many Illustrations. Crown 8vo, cloth, 1s.

London: Ward, Lock, & Co., Warwick House, Dorset Buildings, Salisbury Square, E.C.



### "OUR LITTLE ONES" LIBRARY.

CLOTH GILT, ILLUSTRATED,

- 1 **LITTLE MISS MISCHIEF, AND OTHER STORIES.** By SUSAN COOLIDGE, Author of "The New Year's Bargain," "What Katy Did," &c. With Illustrations by ADDIE LEDYARD. 3s. 6d.
  - 2 **MORAL NURSERY TALES FOR CHILDREN.** By the Author of "The Golden Harp." 3s. 6d.
- This little book contains Stories for Children, each inculcating a Lesson without obtruding it. The Stories have been chosen with a due regard to variety, and are fully Illustrated.*
- 3 **HOLIDAY HOUSE.** By CATHERINE SINCLAIR. Illustrated. 3s. 6d.
  - 4 **THE STORY OF STORIES; or, Bible Narratives for the Young.** By Mrs. LEATHLEY, Author of "Chickseed without Chickweed." Beautifully illustrated with full-page Engravings. 416 pages. 3s. 6d.
  - 5 **THE CHILD'S OWN BOOK OF COUNTRY PLEASURES.** Sixteen Coloured and numerous other Illustrations. 3s. 6d.
  - 6 **FANNY FERN'S NEW STORIES FOR CHILDREN.** By the Author of "Fern Leaves." Illustrated. 3s. 6d.
  - 7 **GOOD OLD STORIES AND FAIRY TALES.** Told for the Hundredth Time by H. W. DULCKEN, Ph.D. Eight Coloured and numerous other Illustrations. 3s. 6d.
  - 8 **OLD NURSERY TALES AND FAMOUS HISTORIES.** Re-told by H. W. DULCKEN, Ph.D. Illustrated with 8 Coloured, and 130 other Illustrations. 3s. 6d.
  - 9 **HARRY'S LADDER TO LEARNING.** 230 Engravings, and 16 Coloured Plates. 5s.
  - 10 **SONGS FOR THE LITTLE ONES AT HOME.** Sixteen Coloured and many other Illustrations. 5s.

London: Ward, Lock, & Co., Warwick House, Dorset Buildings, Salisbury Square, E.C.



**"OUR LITTLE ONES" LIBRARY—continued.**

11. **HALF-HOURS WITH THE BIBLE**; or, Scripture Scenes and Characters; described in a simple and attractive form, suitable for Young People; upwards of 150 Engravings. 5s.
12. **BRAVE OLD BALLADS (THE BOOK OF)**. With 16 Coloured Illustrations, from designs by John Gilbert. 5s.  
*"I never heard the old song of 'Percie and Douglas' that I found not my heart moved more than with the trumpet."—SIR PHILIP SYDNEY.*
13. **NURSERY SONGS AND BALLADS**. Uniform with "Harry's Ladder." Eight Coloured Cuts and numerous Plain Illustrations. 5s.
14. **LITTLE MARY'S NURSERY STORY BOOK**. With numerous Illustrations. 5s.
15. **NURSERY TALES AND STORIES**. Uniform with "Songs for the Little Ones." Eight Coloured Cuts and numerous Plain Illustrations. 5s.
16. **PAPA'S PRETTY GIFT-BOOK FOR ALL GOOD LITTLE BOYS AND GIRLS**. With 150 clever Engravings. 3s. 6d.
17. **NURSERY RHYMES, OLD AND NEW**. A collection of all the most favourite Nursery Rhymes, Jingles, and Stories: also many new ones, now for the first time printed. Numerous clever and characteristic Illustrations. 5s.
18. **SHORT STORIES AND POEMS FOR CHILDREN**. Original and select, with numerous Wood Engravings. New and Revised Edition, 3s. 6d.

**BEETON'S PENNY CHILDREN'S BOOKS.**

*As Elementary Books for Children, none will be found better calculated to meet the end in view. Every step of the way being made cheerful by Pictures, and the Lessons advancing by easy gradations, make this series full of attractions to young beginners.*

1. **BEETON'S PICTORIAL A B C BOOK**. 28 pages. Comprising Alphabet of Animals, Alphabet of Objects, Small and Capital Letters, Script Letters, Alphabet of Country Life, All about the Alphabet told in Verse, &c. With 94 Illustrations.
2. **BEETON'S PICTORIAL SPELLING BOOK**. 24 pp. Comprising Easy Words of Two Letters to Words of Seven Syllables. 43 Illustrations.
3. **BEETON'S PICTORIAL PRIMER AND EASY WORD BOOK**. 24 pp. Comprising Easy Words and Easy Reading Lessons from Words of Two to Six Letters. 78 Illustrations.
4. **BEETON'S PICTORIAL READER**. 24 pp. Comprising Reading Lessons in Prose and Poetry of an interesting and Progressive Character. 21 Illustrations.
5. **BEETON'S PICTORIAL HISTORY OF ENGLAND**. 28 pp. Comprising Lessons about English Kings, Chronologically Arranged. Also a List of the Kings and Queens of England, with the Dates when their Reigns began and ended. 46 Illustrations.
6. **BEETON'S PICTORIAL BIBLE HISTORY**. 28 pp. Comprising First Lessons from Bible History, from the Fall of Adam to the time of the Apostles. 39 Illustrations.

**THE CHILD'S PICTURE BIBLE STORIES.** Royal 8vo, 2d.; coloured, 3d.

- |   |   |
|---|---|
| 1. LIFE AND TEACHINGS OF OUR LORD JESUS CHRIST. | 4. THE STORY OF THE MIGHTY MEN OF ISRAEL.   |
| 2. FROM THE CREATION TO THE DELUGE.             | 5. THE HISTORY OF DAVID.                    |
| 3. THE HISTORY OF ABRAHAM, ISAAC, AND JACOB.    | 6. THE APOSTLES AND OUR SAVIOUR'S TEACHING. |

*London: Ward, Lock, & Co., Warwick House, Dorset Buildings, Salisbury Square, E.C.*





### THE "LITTLE PET" SERIES.

*The Cheapest Series of Children's Books ever Published.*  
Picture Boards, 2s.; Cloth, 2s. 6d.

1. **OUR LITTLE PET'S OWN PICTURE BOOK.** With 160 illustrations, especially adapted for Children.
2. **NEW COMICAL NURSERY RHYMES AND STORIES TO MAKE LITTLE CHILDREN LAUGH.** Numerous characteristic engravings.
3. **PRETTY LITTLE LESSONS FOR PRETTY LITTLE CHILDREN.** Illustrated with 250 pretty pictures.
4. **EASY TALES AND PLEASANT STORIES FOR OUR YOUNG FRIENDS.** Embellished with upwards of 200 engravings.
5. **BIBLE SKETCHES FROM THE OLD AND NEW TESTAMENTS,** adapted for juvenile reading. With about 80 illustrations.
6. **SACRED READINGS FOR YOUNG CHILDREN.** Selected from the Old Testament. With about 60 engravings.
7. **THE CHILD'S OWN BOOK OF PICTURES, TALES, AND POETRY.** Numerous pictures, engraved title and frontispiece.
8. **FAVOURITE NURSERY RHYMES FOR NURSERY FAVOURITES.** With about 200 engravings.
9. **MERRY RHYMES AND STORIES FOR MERRY LITTLE LEARNERS.** With laughable pictures.
10. **LITTLE FANNY'S NURSERY PICTURE BOOK.** Super-royal 16mo, numerous coloured illustrations.

**BIBLE STEPS FOR LITTLE PILGRIMS;** or, Scripture Stories for Little Folks. Beautifully illustrated with 16 Coloured Pictures and Engravings in the text. Imperial 16mo, handsomely bound in cloth gilt, 5s.

**SACRED STORIES FOR SUNDAY HOURS;** or, Scripture Narratives from the Old Testament. With Coloured Pictures. Imperial 16mo, cloth gilt, 3s. 6d.

**THE GOOD SHEPHERD;** or, The Story of Jesus and His Apostles, for the Young. With Coloured Pictures. Imperial 16mo, cloth gilt, 2s. 6d.

*London: Ward, Lock, & Co., Warwick House, Dorset Buildings, Salisbury Square, E.C.*



### THE GOOD GIFT LIBRARY FOR LITTLE PEOPLE.

There are no books more suitable for children than these. Of a high moral tone, combined with most interesting tales and poetry, they not only set forth the advantages of being "good," but they impart a reverence and love for the Creator and His works, while their cheapness brings them within the reach of all.

Pott 8vo, cloth gilt, Illustrated, price 6d. each.

1. **LITTLE SUSY'S LITTLE SERVANTS.** 1st Series. By the Author of "Stepping Heavenward."
2. **LITTLE SUSY'S LITTLE SERVANTS.** 2nd Series. By the Author of "Stepping Heavenward."
3. **LITTLE SUSY'S BIRTHDAYS.** 1st Series. By the Author of "Stepping Heavenward."
4. **LITTLE SUSY'S BIRTHDAYS.** 2nd Series. By the Author of "Stepping Heavenward."
5. **LITTLE SUSY'S TEACHERS.** 1st Series. By the Author of "Stepping Heavenward."
6. **LITTLE SUSY'S TEACHERS.** 2nd Series. By the Author of "Stepping Heavenward."
7. **ORIGINAL POEMS.** 1st Series. By Ann and Jane Taylor.
8. **ORIGINAL POEMS.** 2nd Series. By Ann and Jane Taylor.
9. **ORIGINAL POEMS.** 3rd Series. By Ann and Jane Taylor.
10. **WATTS' DIVINE AND MORAL SONGS.**

— ♦ —

**THE KINDERGARTEN SYSTEM;** or, Toy Teaching and Play Learning.  
A Manual of the German Healthy and Happy Method for the Mental and Physical Education of young children. Illustrated. Crown 8vo, paper boards, 2s.

London: Ward, Lock, & Co., Warwick House, Dorset Buildings, Salisbury Square, E.C.





**BUNYAN'S PILGRIM'S PROGRESS** From this World to That Which is to Come. By JOHN BUNYAN. With a Memoir of the Author, by W. H. DULCKEN, Ph.D. With 100 page and other Illustrations by Thomas Dalziel, and engraved by the Brothers Dalziel.

This Volume is full of chaste and beautiful Engravings, contains the entire text, printed in clear, large type, and is bound in a style of surpassing excellence. 4to, cloth gilt, gilt edges, 10s. 6d. Post 8vo Editions, printed on toned paper, extra cloth gilt, and gilt edges, with 100 Illustrations by the Brothers Dalziel, 3s. 6d. In cloth gilt, bevelled boards, with 100 Illustrations by the Brothers Dalziel, 2s. 6d.

\* \* The Cheapest and Best Editions Published.

**CHILD'S (THE) POPULAR FAIRY TALES.** Sixteen Coloured and other Illustrations by DALZIEL BROTHERS. Imperial 16mo, 420 pp., large type, cloth extra, red edges, 5s.

CONTENTS:—Tom Thumb, The Three Bears, Ali Baba and the Forty Thieves, Robin Hood, Puss in Boots, Jack and the Bean Stalk, The Sleeping Beauty, Little Red Riding Hood, Jack the Giant Killer, Cinderella, Beauty and the Beast, Little Goody Two-Shoes, Aladdin.

**CHILD'S (THE) BOOK OF FRENCH AND ENGLISH.** Comprising One Hundred and Two Lessons in Words and Phrases, French and English, line for line. With Reading Book of Simple Stories in French, for the use of Children of both sexes, from Six to Twelve years old. Appropriately Illustrated with Designs, which, of themselves, form Models for Drawing. Imperial 16mo, cloth gilt, 5s.

London: Ward, Lock, & Co., Warwick House, Dorset Buildings, Salisbury Square, E.C.



### FIVE SHILLING PICTURE BOOKS.

**AUNT FANNY'S NURSERY TALES AND RHYMES** (mounted on linen).  
With full-page Illustrations printed in colours.

**AUNT FANNY'S PICTURE PRESENT BOOK.** A Book of Simple Stories for Children. With many Illustrations.

**AUNT FANNY'S PRETTY PICTURE BOOK.** With full-page Illustrations printed in Colours (mounted on strong linen).

**CHILDREN'S PICTORIAL MUSEUM OF BIRDS, BEASTS, AND FISHES.** With 16 Coloured Plates by Harrison Weir, and 200 Engravings in the text.

**CHILD'S OWN BOOK OF SCRIPTURE PICTURES, OLD TESTAMENT.**

**CHILD'S OWN BOOK OF SCRIPTURE PICTURES, NEW TESTAMENT.**

**BIBLE STEPS FOR LITTLE PILGRIMS.** In Separate Books. Imp. 16mo, in coloured wrapper, 6d. each.

- |  |                               |
|--|-------------------------------|
| 1. THE STORY OF THE CREATION AND THE DELUGE. | 5. THE STORY OF THE JUDGES.   |
| 2. THE STORY OF ABRAHAM, ISAAC, AND JACOB.   | 6. THE STORY OF DAVID.        |
| 3. THE STORY OF JOSEPH AND HIS BROTHERS.     | 7. THE STORY OF THE PROPHETS. |
| 4. THE STORY OF MOSES.                       | 8. THE LIFE OF JESUS.         |
|  | 9. STORIES OF THE PARABLES.   |
|  | 10. STORIES OF THE MIRACLES.  |
|  | 11. STORIES OF THE APOSTLES.  |

### PICTURE BOOKS.

**THE CHILD'S FAMOUS PICTURE BOOK.** Full of Pictures. Cloth gilt, 3s.

**THE ANIMAL PICTURE BOOK FOR KIND LITTLE PEOPLE.**  
With large Coloured Pictures. Cloth, 3s. 6d.

**AUNT FANNY'S NURSERY TALES AND RHYMES.** With full-page Illustrations in colours. Cloth gilt, 3s. 6d.

**AUNT FANNY'S PRETTY PICTURE BOOK.** With full-page coloured Illustrations. Cloth gilt, 3s. 6d.

**THE BOOK OF ANIMALS.** With 9 coloured Illustrations by HARRISON WEIR, and many Engravings. Cloth, 3s. 6d.

**DOMESTIC ANIMALS AND THEIR HABITS.** With descriptive Text by H. W. DULCKEN, Ph.D., and 12 large double-page coloured Illustrations. Boards, 6s.; cloth gilt, 7s.

**WILD ANIMALS AND THEIR HOMES.** With descriptive Text by H. W. DULCKEN, Ph.D., and 12 large double-page coloured Illustrations. Boards, 6s.; cloth gilt, 7s. 6d.

London: Ward, Lock, & Co., Warwick House, Dorset Buildings, Salisbury Square, E.C.



### BEETON'S BOY'S OWN LIBRARY.

Demy 8vo, cloth gilt, price 5s. each; or 6s. gilt edges. They have all been prepared by MR. BEETON with a view to their fitness in manly tone and handsome appearance for Presents for Youth.

1. **STORIES OF THE WARS.** By JOHN TILLOTSON. Coloured Pictures and many other Illustrations.
2. **A BOY'S ADVENTURES IN THE BARONS' WARS;** or, How I Won my Spurs. EDGAR. Coloured Frontispiece and many Illustrations.
3. **CRESSY AND POICTIERS.** EDGAR. Coloured Frontispiece and many Illustrations.
4. **RUNNYMEDE AND LINCOLN FAIR.** EDGAR. Coloured Frontispiece and many Engravings.

London: Ward, Lock, & Co., Warwick House, Dorset Buildings, Salisbury Square, E.C.



*BOY'S OWN LIBRARY—continued.*

5. **WILD SPORTS OF THE WORLD.** GREENWOOD. Eight Coloured Plates and many other Illustrations.
6. **CURIOSITIES OF SAVAGE LIFE.** JAMES GREENWOOD. Illustrated.
7. **HUBERT ELLIS**, a Story of King Richard the Second's Days. Coloured Frontispiece and many Engravings.
8. **DON QUIXOTE.** With nearly 700 Illustrations.
9. **GULLIVER'S TRAVELS.** Coloured Frontispiece and 300 Engravings.
10. **ROBINSON CRUSOE.** Coloured and other Plates and many Woodcuts.
11. **SILAS THE CONJURER.** By JAMES GREENWOOD. Illustrated.
12. **SAVAGE HABITS AND CUSTOMS.** By J. GREENWOOD. Illustrated.
13. **REUBEN DAVIDGER.** By J. GREENWOOD. Illustrated.
14. **BRAVE BRITISH SOLDIERS AND THE VICTORIA CROSS.** Illustrated.
15. **ZOOLOGICAL RECREATIONS.** By W. J. BRODERIP, F.R.S. Coloured Frontispiece and many other Illustrations.
16. **WILD ANIMALS IN FREEDOM AND CAPTIVITY.** Coloured Frontispiece and 120 Illustrations.
18. **THE WORLD'S EXPLORERS**, including the Discoveries of Livingstone and Stanley. Coloured Frontispiece and many Engravings.
19. **THE MAN AND THE MONKEYS;** or, Ninety Days in Apeland. Illustrated by G. Doré.
20. **GOLDEN AMERICAS.** By JOHN TILLOTSON. Illustrated.

—♦—

### *THE YOUTH'S LIBRARY OF WONDERS AND ADVENTURES.*

(Including JULES VERNE'S Works, with Coloured Plates.) Crown 8vo, wrapper, 1s.; cloth gilt, 2s.

1. **A JOURNEY INTO THE INTERIOR OF THE EARTH.** By JULES VERNE. With Three Coloured Plates.
2. **THE ENGLISH AT THE NORTH POLE.** By JULES VERNE. Three Coloured Pictures.
3. **THE ICE DESERT.** By JULES VERNE. Three Coloured Plates.
4. **FIVE WEEKS IN A BALLOON.** By JULES VERNE. Three Coloured Plates.
5. **THE MYSTERIOUS DOCUMENT.** By JULES VERNE. Three Coloured Plates.
6. **ON THE TRACK.** By JULES VERNE. Three Coloured Plates.
7. **AMONG THE CANNIBALS.** By JULES VERNE. Three Coloured Plates.
8. **TWENTY THOUSAND LEAGUES UNDER THE SEA.** By JULES VERNE. Part I. Three Coloured Plates.
9. **TWENTY THOUSAND LEAGUES UNDER THE SEA.** By JULES VERNE. Part II. Three Coloured Plates.
10. **TWO YEARS BEFORE THE MAST.** By R. H. DANA.
11. **FROM THE EARTH TO THE MOON.** By JULES VERNE. Three Coloured Plates.
12. **ROUND THE MOON.** By JULES VERNE. Two Coloured Plates.
13. **SANDFORD AND MERTON.** By THOMAS DAY. Illustrated.
14. **BARON MUNCHAUSEN** (Life, Travels, and Extraordinary Adventures of).

*London: Ward, Lock, & Co., Warwick House, Dorset Buildings, Salisbury Square, E.C.*





**DALZIEL'S ILLUSTRATED ARABIAN NIGHTS' ENTERTAIN-  
MENTS**, with upwards of 200 Illustrations, by J. E. MILLAIS, R.A., J. TENNIEL,  
J. D. WATSON, E. B. HOUGHTON, G. J. PINWELL, and T. DALZIEL, together with initial  
letters, ornamental borders, &c., &c. Engraved by the Brothers DALZIEL. In one handsome  
volume, cloth richly gilt, back, side, and edges, price 21s.

*London : Ward, Lock, & Co., Warwick House, Dorset Buildings, Salisbury Square, E.C.*



## TOY BOOKS.

**WARWICK HOUSE TOY BOOKS.** Carefully Edited and handsomely printed in Colours. Large 4to, in attractive wrapper, 1s.; those marked \* are mounted on strong cloth, 2s.:-

- |   |  |
|---|--|
| <ul style="list-style-type: none"> <li>1. DOMESTIC ANIMALS.</li> <li>2. HOME AND FIELD ANIMALS.</li> <li>*3. NURSERY SONGS AND BALLADS.</li> <li>*7. ADVENTURES WITH ANIMALS.</li> <li>8. THE PICTURE ROBINSON CRUSOE.</li> <li>*9. THE CHILDREN'S HOUSEHOLD PETS.</li> <li>*10. THE CHILDREN'S PICTURE ALPHABET.</li> <li>*12. THE NAUGHTY PUPPIES.</li> <li>*13. A. B. C. OF ANIMALS AND BIRDS.</li> <li>*14. A. B. C. OF PRETTY COUNTRY SCENES.</li> <li>*15. THE NURSERY PICTURE GALLERY AND CHILD'S OWN PICTURE COLOUR BOOK.</li> <li>*16. MASTER MOUSEIE'S SUPPER PARTY; Showing how when Puss is away the Mice will Play. With 6 Coloured Plates by KRONHEIM.</li> <li>*17. AMUSING MAZES, A SET OF PUZZLE PICTURES. Beautiful Illustrations, in Colours, by LEIGHTON BROS.</li> <li>*18. LITTLE RED RIDING HOOD. New Pictures.</li> <li>*19. LITTLE ALFRED'S VISIT TO WOMBWELL'S MENAGERIE; Showing the Menagerie, with other Large Pictures of Various Animals.</li> </ul> | <ul style="list-style-type: none"> <li>*24. PUSS IN BOOTS.</li> <li>*25. THE DISCONTENTED BOY.</li> <li>*26. MAMA'S NEW PICTURE ALPHABET.</li> <li>*27. A. B. C.—BRAVE DEEDS.</li> <li>*28. HOLIDAY ALPHABETS.</li> <li>*29. THE A. B. C. OF ANIMAL LIFE.</li> <li>*30. THE FAIRY WELL; or, The Little Brother and Sister.</li> <li>*31. MISS MOUSEIE'S WEDDING AND BALL.</li> <li>32. THE NURSERY ARTIST; or, The Little Picture Maker. With 6 large Coloured Pictures with figures round the sides, ready for cutting out and pasting down. 1st Series.</li> <li>33. Do. Do. 2nd Series.</li> <li>34. Do. Do. 3rd Series.</li> <li>35. Do. Do. 4th Series.</li> <li>*38. ANIMALS AND THEIR USES.</li> <li>*39. THE THREE FRIENDS OF MAN.</li> <li>*40. ALPHABET OF FAVOURITE ANIMALS.</li> <li>*41. A B C OF NURSERY RHYMES.</li> <li>*42. COCK ROBIN. New Edition.</li> <li>*43. THE CATS' HUNTING PARTY.</li> <li>*44. PRETTY PETS AND HAPPY PLAYMATES.</li> </ul> |
|---|--|

\*.\* This unparalleled series of Toy Books contains exquisite Coloured Pictures, which will alone commend them to every Household. The subjects will please every child, and the variety shown by the titles is sufficient for every taste.

**AUNT FANNY'S SIXPENNY TOY BOOKS.** Royal 8vo, wrapper. With beautiful Coloured Pictures.

- |   |   |
|---|---|
| <ul style="list-style-type: none"> <li>1. THE TWO PUPPIES.</li> <li>2. THE CUNNING FOX.</li> <li>3. THE BOYS AND THE GIANT.</li> <li>4. DICK DOLITTLE, THE IDLE SPARROW.</li> <li>5. ALPHABET OF ANIMALS.</li> <li>6. AUNT FANNY'S A B C.</li> <li>7. COCK ROBIN.</li> <li>8. NURSERY RHYMES ALPHABET.</li> <li>9. AUNT FANNY'S NURSERY RHYMES</li> <li>10. NAUGHTY CHICKENS.</li> <li>11. PUNCH AND JUDY.</li> </ul> | <ul style="list-style-type: none"> <li>12. OLD MOTHER HUBBARD.</li> <li>13. THE BOOK OF ANIMALS.</li> <li>14. THREE LITTLE KITTENS.</li> <li>16. LITTLE MISS TOTTIE'S TRAVELS.</li> <li>17. LITTLE MISS TOTTIE'S CHIMNEY CORNER STORIES.</li> <li>18. LITTLE MISS TOTTIE AND HER FRIENDS.</li> <li>19. ALPHABET OF TOYS.</li> <li>20. ALPHABET OF GAMES.</li> </ul> |
|---|---|

Except Nos. 16, 17, and 18, mounted on strong cloth, 1s.

**AUNT AFFABLE'S TWOPENNY SERIES OF PRETTY PLAY BOOKS.** Royal 8vo, coloured wrappers, plain, 2d.; coloured, 3d.

- |  |   |
|--|---|
| <ul style="list-style-type: none"> <li>1. THE A B C BOOK.</li> <li>2. A B C OF OBJECTS.</li> </ul> | <ul style="list-style-type: none"> <li>3. DEATH AND BURIAL OF COCK ROBIN.</li> <li>4. CHILD'S PICTURE BOOK OF ANIMALS.</li> </ul> |
|--|---|

London: Ward Lock, & Co., Warwick House, Dorset Buildings, Salisbury Square, E.C.





**BEETON'S BOY'S PRIZE LIBRARY.**

As prizes for Young Gentlemen, Birthday Gifts, or Anniversary Rewards. Edited by S. O. BEETON.  
Demy 8vo, cloth gilt, 5s.; gilt edges, 6s.

1. **BEETON'S FACT, FICTION, HISTORY, AND ADVENTURE.** Containing: 'Cressy and Poitiers,' by the late J. G. EDGAR (Illustrated). Papers on Natural History, by the Rev. J. G. WOOD, M.A. (Illustrated). The Adventures of Reuben Davidger, a Tale, by JAMES GREENWOOD (Illustrated). Scientific Articles (Illustrated), &c., &c. 1,110 pp.

London: Ward, Lock, & Co., Warwick House, Dorset Buildings, Salisbury Square, E.C.



*BEETON'S BOY'S PRIZE LIBRARY—continued.*

2. **BEETON'S HISTORICAL ROMANCES, DARING DEEDS, AND ANIMAL STORIES.** Containing: Runnymede and Lincoln Fair, by the late J. G. EDGAR. Antony Waymouth; or, The Gentlemen Adventurers, by WILLIAM H. G. KINGSTON. The Zoological Gardens, by the Rev. J. G. WOOD. King Lion. Sports and Pastimes. Poetry, Puzzles, &c. &c. 1,104 pp., with 34 Full-page Engravings, and 250 Woodcuts.
3. **BEETON'S BRAVE TALES, BOLD BALLADS, AND TRAVELS BY LAND AND SEA.** Containing: Historical Stories, by W. H. D. ADAMS. Hubert Ellis. Ingonyama, the Caffre Chief, by Captain DRAYSON. Highland Regiments as they Once Were. King of Trumps. Poems by BERANGER, &c., &c. 1,088 pp., with 38 Full-page Engravings and 320 Cuts.
4. **BEETON'S TALES OF CHIVALRY.** School Stories, Mechanics at Home, and Exploits of the Army and Navy. 888 pages, with Twenty-three full-page Engravings, on toned paper, and 255 woodcuts.
5. **BEETON'S HERO SOLDIERS, SAILORS, AND EXPLORERS.** Gymnastics, Telegraphy, Fire Arms, &c. 890 pages, with Thirty-six full-page Engravings on toned paper, and 157 Woodcuts.
6. **BEETON'S FAMOUS VOYAGES, BRIGAND ADVENTURES, TALES OF THE BATTLEFIELD,** &c. 1,054 pp., with Thirty-eight Plates and 156 Woodcuts inserted in the Text.
7. **BEETON'S VICTORIOUS ENGLISH SEA STORIES, TALES OF ENTERPRISE AND SCHOOL LIFE.** 1,050 pp., with 46 Full-page Plates and 150 Woodcuts in the Text.

---

### *THE BOY'S FAVOURITE LIBRARY.*

Crown 8vo, cloth, gilt edges, price 3s. 6d. Each volume well Illustrated.

*Boys love to read the records of adventurous deeds, to trace the careers of brave and good lads who have attained to eminence, and to be told of wonderful natural objects. The volumes in this series furnish the literary food most acceptable to intelligent and spirited boys, and most calculated to develop their best qualities.*

1. **THE WONDERS OF THE WORLD,** in Earth, Sea, and Sky. 123 Engravings.
2. **FIFTY CELEBRATED MEN.** Many Wood Engravings.
3. **ROBINSON CRUSOE.** By DANIEL DE FOE. With many Engravings.
4. **SANDFORD AND MERTON.** By THOMAS DAY. With 100 Illustrations by DALZIELS.
5. **A BOY'S LIFE ABOARD SHIP,** as it is told by Himself. With Full-page Illustrations.
6. **LIFE IN A WHALER;** or, Perils and Adventures in the Tropical Seas. By SAILOR CHARLEY. With Full-page Illustrations.
7. **GREAT INVENTORS;** the Sources of their Usefulness, and the Results of their Efforts. With 109 Engravings.
8. **HOUSEHOLD STORIES.** By the Brothers GRIMM, &c. Profusely Illustrated.
9. **THE MARVELS OF NATURE;** or, Outlines of Creation. By ELISHA NOXCE. With 400 Engravings by the Brothers DALZIEL.

*London: Ward, Lock, & Co., Warwick House, Dorset Buildings, Salisbury Square, E.C.*

**BOY'S FAVOURITE LIBRARY**—*continued.*

Price 3s. 6d. per Volume.

10. **THE BOY'S BOOK OF INDUSTRIAL INFORMATION.** With 365 Engravings by DALZIEL Bros.
11. **FAMOUS BOYS,** and how they became Famous Men. By the Author of "Clever Boys." With many Engravings.
12. **THE TRIUMPHS OF PERSEVERANCE AND ENTERPRISE.** Numerous Illustrations.
13. **EDGAR'S CRUSADES AND CRUSADERS.** With Full-page Illustrations.
14. **THE MERCHANT'S CLERK;** or, Mark Wilton. A Book for Young Men. By the Rev. C. B. TAYLER, M.A. With Full-page and other Illustrations.
15. **SAILOR HERO;** or, The Frigate and the Lugger. With Illustrations. By Captain F. C. ARMSTRONG.
16. **CRUISE OF THE DARING.** A Tale of the Sea. With Illustrations. By Captain F. C. ARMSTRONG.
17. **PYROTECHNY;** or, The Art of Making Fireworks. With 124 Illustrations of Forms and Diagrams for Manufacture and Exhibition.
18. **MONT BLANC, A BOY'S ASCENT OF.** By ALBERT SMITH. Illustrated. With a Memoir of the Author, by EDMUND YATES.
19. **POE'S TALES OF MYSTERY, IMAGINATION, AND HUMOUR.**
21. **BOY'S BOOK OF MODERN TRAVEL AND ADVENTURE.** By MEREDITH JONES. Illustrated.
22. **THE YOUNG MAROONERS.** By F. R. GOULDING. Illustrated.
22. **ANTONY WAYMOUTH;** or, The Gentlemen Adventurers. By WILLIAM H. G. KINGSTON. With Full-page Illustrations.

---

**BEETON'S PICTORIAL SPELLER.** The cheapest Illustrated Spelling Book published. 196 pages, and 430 Illustrations. Crown 8vo, cloth plain, 1s.

**GOLDEN CHILDHOOD ANNUAL, 1875.** Full of beautiful Pictures, pretty Stories, Songs for the Little Ones, Fairy Tales, Nursery Rhymes, with Music for the Pianoforte. With a set of Paper Patterns for a Complete Dolly's Outfit. Imp. 16mo, picture boards, 3s. Cloth gilt, 3s. 6d. Extra Edition, gilt edges, with Coloured Pictures, 5s.

**MERRY SUNBEAMS** ("GOLDEN CHILDHOOD" ANNUAL for 1876). The Book contains Charming Pictures, Pretty Stories, Fairy Tales, Children's Songs, with Music, &c. In picture boards, 3s. Handsomely bound in cloth gilt, gilt edges, with chromo frontispiece, 5s.

**GOLDEN CHILDHOOD FOR 1877.** Much enlarged and improved in every way, with more Stories and Tales, more Instructive Articles, more Songs and Music, more Pastime pages, and many more Pictures. Imperial 16mo, picture boards, 3s.; cloth gilt, gilt edges, with charming Coloured Picture, 5s.

**ANN AND JANE TAYLOR'S POETRY FOR CHILDREN.** Containing the Original Poems, Hymns for Infant Minds, and Rhymes for the Nursery. With many Illustrations. Crown 8vo, handsome cloth gilt, 3s. 6d.

---

*London: Ward, Lock, & Co., Warwick House, Dorset Buildings, Salisbury Square, E.C.*



**BOY'S HANDY BOOK OF GAMES, SPORTS, PASTIMES, AND AMUSEMENTS.** A complete Cyclopaedia of boyish recreative pursuits of every description. 348 pages, with hundreds of Illustrations. Extra cloth gilt, gilt edges, 5s.

**BOY'S HANDY BOOK OF NATURAL HISTORY.** Edited by H. W. DULCKEN, Ph.D. With numerous Illustrations by W. HARVEY and others, and 16 Coloured Plates. Cloth extra gilt, 5s.

**BOY'S OWN SEA STORIES.** Numerous Illustrations. Cloth gilt, gilt edges, 5s.

**BOY'S OWN TREASURY.** 448 pages, and nearly 700 engravings. Cloth gilt, gilt edges, 5s.

Royal 4to, in beautiful floral wrapper, 2s. 6d.; handsome cloth gilt, 3s. 6d.

**THE CHILDREN'S FORGET ME NOT.** A Book of Pictures and Stories for the Young. Containing Stories of the Months, Tales about Animals, Seaside Ditties, &c., with upwards of 100 large Engravings.

This charming volume has been prepared with the greatest care, and will be found to contain all that is most attractive to Little Folks. Printed in handsome type, abounding in pictures, and in a beautiful floral-cover by EDMUND EVANS, the CHILDREN'S FORGET ME NOT will be acknowledged the handsomest and cheapest gift-book of the season. Boards, 2s. 6d.; cloth gilt, 3s. 6d.

**THE SUNNY HOME.** By MERCIE SUNSHINE. The Story of a United Family, with their Adventures at Home and Abroad. This book gives a lively record of the daily life of the Allen family. It combines much pleasant instruction in various subjects specially adapted for children of both sexes, and a record of their stirring adventures and pleasant travel. It is profusely illustrated, and will be found a most attractive present for boys and girls. Imperial 16mo, picture boards, 1s.; handsomely cloth gilt, 2s.

Just Ready, uniform with the above.

**THE SUNNY HOME, SECOND SERIES.** By MERCIE SUNSHINE. Profusely and Beautifully Illustrated. Picture boards, price 1s.; cloth gilt, 2s.

## TOY BOOKS.

New and Handsome Series of Juvenile Books.

**THE PLAYHOUR PICTURE BOOKS.** Large 4to, splendidly printed in Colours, in very handsome binding, cloth gilt extra, 5s.:-

1. NURSERY RHYMES, A B C BOOK.
2. LITTLE FOLKS' BEAUTY PICTURES.
3. LITTLE TOT'S PLEASURE BOOK.

4. CHILD'S OWN PICTURE BOOK OF ANIMALS.
5. THE NURSERY FRIEND.

**GRACIE GOODCHILD'S PRETTY PICTURE BOOKS.** Handsomely printed in Colours. Coloured wrapper, 3d. each.:-

1. THE PRETTY PICTURE ALPHA-BET.
2. THE PRETTY PICTURE A B C.

3. THE PRETTY PICTURE PRIMER.
4. THE PRETTY PICTURE NURSERY RHYMES.

**WARD, LOCK, AND CO.'S SIXPENNY COLOURED INDESTRUCTIBLE BOOKS.** Mounted on strong linen, 6d. each.:-

1. EASY A B C BOOK.
2. LARGE LETTER A B C.

3. EASY WORDS AND PRETTY PICTURES.
4. EASY NURSERY RHYMES.

London: Ward, Lock, & Co., Warwick House, Dorset Buildings, Salisbury Square, E.C.



# WARD AND LOCK'S JUVENILE PUBLICATIONS.

## WARWICK HOUSE TOY BOOKS.

*Messrs. WARD, LOCK & CO. have much pleasure in calling attention to this popular series of amusing and instructive books for nursery and play-room use. These comprise many old and favourite tales, poems, and jingles, interspersed with newer and equally attractive matter. It has been the constant endeavour of the publishers to combine, in this series, the instructive with the amusing element, wherever this could be effected without taking away, or even lessening, the charm of the books as vehicles for recreation. Great care has been taken to render them worthy to be—what it is confidently hoped they will become—THE MOST POPULAR CHILDREN'S TOY BOOKS OF THE DAY.*

Large 4to., handsome wrapper, price 1s. each; those marked thus (\*) can also be had mounted on linen, 2s. each.

1. Domestic Animals. With Coloured Plates and other Illustrations.
2. Home and Field Animals. With Coloured Plates and other Illustrations.
- \*3. Nursery Songs and Ballads. With Coloured Illustrations.
- \*7. Adventures with Animals. With Coloured Pictures.
- \*8. The Picture Robinson Crusoe. Coloured Pictures.
- \*9. The Children's Household Pets. With Coloured and other Illustrations.
- \*10. The Children's Picture Alphabet. Coloured Pictures.
- \*12. The Naughty Puppies. With Coloured Illustrations.
- \*13. The A B C of Animals and Birds. Coloured Illustrations.
- \*14. The A B C of Pretty Country Scenes. Coloured Illustrations.
- \*15. The Nursery Picture Gallery and Child's Own Picture Colour Book. With 6 Coloured Plates and Outlines for Copying same.
- \*16. Master Mousie's Supper Party: Showing how when Puss is away the Mice will Play. With 6 Coloured Plates.
- \*17. Amusing Mazes; a Set of Puzzle Pictures. Coloured Pictures.
- \*18. Little Red Riding Hood. With Coloured Pictures.
- \*19. Little Alfred's Visit to Wombwell's Menagerie. Coloured Pictures of the Menagerie and the various Animals.
- \*24. Puss in Boots. With Coloured Illustrations.
- \*25. The Discontented Boy. With Coloured Illustrations.
- \*26. Mamma's New Picture Alphabet. With Coloured Plates.
- \*27. A B C of Heroes. Coloured Pictures.
- \*28. Holiday Alphabet. Coloured Pictures.
- \*29. The Alphabet of Animal Life. With Coloured Pictures.
- \*30. The Fairy Well; or, The Little Brother and Sister. With Coloured Illustrations.
- \*31. Miss Mousie's Wedding and Ball. With Coloured Pictures.
- \*32. The Nursery Artist; or, The Little Picture Maker. 1st Series. With 6 large Coloured Pictures with figures round the sides, ready for cutting out and pasting down.
33. The Nursery Artist. 2nd Series.
34. The Nursery Artist. 3rd Series.
35. The Nursery Artist. 4th Series.
- \*38. Favourite Animals and their Uses. With Coloured Illustrations.
- \*39. The Three Friends of Man. With Coloured Illustrations.
- \*40. Alphabet of Favourite Animals. With Coloured Illustrations.
- \*41. A B C of Nursery Rhymes. Coloured Illustrations.
- \*42. Cock Robin. New Edition, with Coloured Illustrations.
- \*43. The Pussy-Cat's Hunting Party. Beautifully printed in Colours.
- \*44. Pretty Pets and Happy Playmates. Beautifully printed in Colours.
- \*45. Hoppety Frogs and Nibbledy Mice. Beautifully printed in Colours.

London: WARD, LOCK and Co., Warwick House, Salisbury Square, E.C.

# WARD AND LOCK'S JUVENILE PUBLICATIONS.

## THE LOTTIE LIGHTHEART SERIES.

In picture boards, price 2s. each; those marked (\*) can also be had bound in cloth gilt, price 3s.

1. **Brave Old Ballads.** A Collection of Popular Ballads for Children's Reading. With Coloured Plates.
- 2 **Robin Hood, and other Ballads.** With Coloured Plates from Drawings by JOHN GILBERT.
3. **Moral Nursery Tales for Children.** By the Author of "The Golden Harp," &c. With many Illustrations.
4. **Children's Nursery Tales.** By the Author of "The Golden Harp," &c. With many Illustrations.
- \* 5. **Charlie and Rosie.** A Book of Picture Stories, Poetry, and Music. With about 100 Illustrations.
- \* 6. **Lottie Lighthouse.** Containing Children's Tales and Stories, and about 100 Pictures.
- \* 7. **The Happy Home Picture Book.** A never-failing source of Interest and Amusement for the Young. With about 100 Illustrations.
- \* 8. **Sunny Child Life; or, Louisa Manners.** Containing many interesting Stories for the Young. With about 100 Illustrations.
- \* 9. **The Primrose Picture Book.** Full of Useful Information and Amusement for Little People. With nearly 200 Pictures.
- \* 10. **My Little Friend.** A Pleasant Companion for Children. Illustrated with nearly 200 Engravings.
- \* 11. **The Daisy Picture Book.** Being the "Golden Childhood" Volume for Midsummer, 1878. Containing pretty Stories, Nursery Rhymes, and everything interesting to Children. With about 200 Illustrations.
- \* 12. **The Keepsake Picture Book.** Being the "Golden Childhood" Volume for Christmas, 1878. A Charming Presentation Book. With about 200 Illustrations.

## THE LITTLE PET SERIES.

Profusely Illustrated, boards, 2s. ; cloth, 2s. 6d.

1. **Our Little Pet's Own Picture Book.** With 160 Illustrations, especially adapted for Children.
2. **New Comical Nursery Rhymes and Stories to Make Little Children Laugh.** Numerous characteristic engravings.
3. **Pretty Little Lessons for Pretty Little Children.** Illustrated with 250 pretty Pictures.
4. **Easy Tales and Pleasant Stories for our Young Friends.** Embellished with upwards of 200 Engravings.
5. **Bible Sketches from the Old and New Testaments,** adapted for Juvenile Reading. With about 80 Illustrations.
6. **Sacred Readings for Young Children.** Selected from the Old Testament. With about 60 Engravings.
8. **The Child's Own Book of Pictures, Tales, and Poetry.** With many Illustrations.
9. **Favourite Nursery Rhymes for Nursery Favourites.** With about 200 Engravings.
10. **Merry Rhymes and Stories for Merry Little Learners.** With many Laughable Pictures.
- \* 11. **Little Fanny's Nursery Picture Book.** With numerous Coloured Illustrations.

London: WARD, LOCK and Co., Warwick House, Salisbury Square, E.C.



# WARD AND LOCK'S JUVENILE PUBLICATIONS.

## WARD, LOCK & CO.'S "GOOD AIM" BOOKS.

*The feature of this series of Books is to encourage in childhood a spirit of Love, Gentleness, and Cheerfulness, while affording amusement and interest.*

Elegantly bound, cloth gilt, price 1s. ; or bevelled boards, gilt edges, 1s. 6d. each.

1. **The Original Poems for Children.** By ANN and JANE TAYLOR. With Coloured Frontispiece.
2. **The Basket of Flowers; or, Piety and Truth Triumphant.** With Coloured Frontispiece.
3. **Ellen's Idol.** By the Author of "Tiny." With Frontispiece.
5. **Sermons on the Wall.** By JOHN TILLOTSON. Illustrated.
6. **Goldy and Goldy's Friends.** By MARY DENSEL. Illustrated.
7. **The One Thing Needful; or, Ethel's Pearls.** Illustrated.
8. **I Don't Know How.** By E. STUART PHELPS. Illustrated.
9. **Sayings and Doings of Children.** By the Rev. J. B. SMITH. Illustrated.
10. **Tiny.** By ELIZABETH STUART PHELPS. With Coloured and other Illustrations.
11. **Tiny's Sunday Nights.** By E. STUART PHELPS. With Coloured and other Illustrations.
12. **The Orphan Boy; or, from Peasant to Prince.** Illustrated.
13. **Tom, Tom, the Printer's Son; A Boy's Story.** Related by Himself. Illustrated.
14. **Only a Dandelion.** By the Author of "Stepping Heavenward." With Coloured and other Illustrations.
15. **Follow Me.** By the Author of "Stepping Heavenward." Illustrated.
16. **New Year's Bargain.** By SUSAN COOLIDGE. Illustrated.
17. **In the Beginning; or, from Eden to Canaan.** Illustrated.
18. **Conquerors and Captives; or, from David to Daniel.** Illustrated.
19. **The Star of Promise; or, from Bethlehem to Calvary.** Illustrated.
20. **The History of the Robins.** By Mrs. TRIMMER. With Coloured Frontispiece.
21. **Hymns for Infant Minds.** By ANN and JANE TAYLOR. Illustrated.
22. **Rhymes for the Nursery.** By ANN and JANE TAYLOR. Illustrated.
23. **Little Susy's Six Birthdays.** By the Author of "Stepping Heavenward." With many Engravings.
24. **Little Susy's Little Servants.** By the Author of "Stepping Heavenward." With Coloured Frontispiece and many Engravings.
25. **Little Susy's Six Teachers.** By the Author of "Stepping Heavenward." With Coloured Frontispiece and many Engravings.
26. **On'y a Penny; or, One of the Least of These.** By the Author of "A Trap to Catch a Sunbeam." With many Illustrations.

London: WARD, LOCK and Co., Warwick House, Salisbury Square, E.C.

